

CONSTRUCTION CONTRACTS

15. Award CC-0569-06/TLR – Airport Boulevard Phase II & III to Hubbard Construction Co., Orlando (\$22,972,100.20).

CC-0569-06/TLR will provide for all labor, materials, equipment, transportation, coordination and incidentals necessary for the construction of a four lane urban roadway section approximately 3.61 miles in length. The roadway plans are separated into two phases. Phase II is approximately 1.70 miles in length from US 17-92 to CR 46A. Phase III is approximately 1.91 miles in length from CR 46A to SR 46. Approximately 1.61 of the 1.91 miles of Phase III is new roadway construction.

This project was publicly advertised and the County received four (4) responses. The Review Committee consisting of Jerry Matthews, Principal Coordinator, Antoine Khoury, Principal Engineer, and William Glennon, Principal Engineer, reviewed the responses. Consideration was given to the bid price, qualifications and experience.

The Review Committee recommends award of the contract to the lowest priced, responsive, responsible bidder, Hubbard Construction Company, in the amount of \$22,972,100.20. The completion time for this project is seven hundred sixty (760) calendar days from issuance of the Notice to Proceed by the County.

This is a budgeted project and funds will be available in conjunction with a BCR approved this same day in account number 077515/077521.560670, CIP 006102. Public Works/Engineering and Fiscal Services/Purchasing and Contracts Division recommend the Board to approve the project and authorize the Chairman to execute the agreement as prepared by the County Attorney's Office.

B.C.C. - SEMINOLE COUNTY, FL
BID TABULATION SHEET

BID NUMBER: CC-0569-06/TLR

BID TITLE: Airport Boulevard Phase II and III

OPENING DATE: March 22, 2006 2:00 P.M.

PAGE: 1 of 2

ALL BIDS ACCEPTED BY SEMINOLE COUNTY ARE SUBJECT TO THE COUNTY'S TERMS AND CONDITIONS AND ANY AND ALL ADDITIONAL TERMS AND CONDITIONS SUBMITTED BY THE BIDDERS ARE REJECTED AND SHALL HAVE NO FORCE AND EFFECT. BID DOCUMENTS FROM THE VENDORS LISTED HEREIN ARE THE ONLY BIDS RECEIVED TIMELY AS OF THE ABOVE OPENING DATE AND TIME. ALL OTHER BID DOCUMENTS SUBMITTED IN RESPONSE TO THIS SOLICITATION, IF ANY, ARE HEREBY REJECTED AS LATE.

ITEM DESCRIPTION	Response 1	Response 2	Response 3
	Hubbard Construction Co. 1936 Lee Road Winter Park, FL 32854 Jean-Noel Velly, Sr. VP PH. 407 645-5500 FX. 407 623-3865	Cherry Hill Construction, Inc. 8211 Washington Blvd Jussup, MD 20794 John A. Loftus, Pres./CEO PH. 410-799-3577 Fx. 410-799-5548	The Middlesex Corp. One Spectacle Pond Rd. Littleton, MA 01460 David Socci, VP 978-742-4400 Fx. 978-742-4434
A = BID TOTAL B = NUMBER OF DAYS A + B COMPUTATION	\$22,972,100.20 760 days \$25,936,100.20	\$26,561,676.57 764 days \$29,541,276.57	\$29,664,229.15 765 \$32,647,729.15
Acknowledge Addenda (3)	Yes	Yes	Yes
Bid Bond	Yes	Yes	Yes
Trench Safety Act	Yes	Yes	Yes
Bidder Information Form	Yes	Yes	Yes
Experience of Bidder	Yes	Yes	Yes
Non-Collusion Affidavit	Yes	Yes	Yes
Certificate of Nonsegregated Facilities	Yes	Yes	Yes
American w/Disabilities Affidavit	Yes	Yes	Yes

THE APPARENT LOW BIDDER IS DETERMINED BY THE A + B COMPUTATION

Opened and Tabulated by: T. Roberts, CPPB

Posted: 03/23/2006

Recommendation: TBD

B.C.C. - SEMINOLE COUNTY, FL
BID TABULATION SHEET

BID NUMBER: CC-0569-06/TLR

BID TITLE: Airport Boulevard Phase II and III

OPENING DATE: March 22, 2006 2:00 P.M.

PAGE: 2 of 2

ALL BIDS ACCEPTED BY SEMINOLE COUNTY ARE SUBJECT TO THE COUNTY'S TERMS AND CONDITIONS AND ANY AND ALL ADDITIONAL TERMS AND CONDITIONS SUBMITTED BY THE BIDDERS ARE REJECTED AND SHALL HAVE NO FORCE AND EFFECT. BID DOCUMENTS FROM THE VENDORS LISTED HEREIN ARE THE ONLY BIDS RECEIVED TIMELY AS OF THE ABOVE OPENING DATE AND TIME. ALL OTHER BID DOCUMENTS SUBMITTED IN RESPONSE TO THIS SOLICITATION, IF ANY, ARE HEREBY REJECTED AS LATE.

ITEM DESCRIPTION	Response 4		
	Prince 5411 Willis road Palmetto, FL 34221 Douglas A. Delaney, VP PHh. 941-722-7707 Fx. 941-722-4641		
A = BID TOTAL B = NUMBER OF DAYS A + B COMPUTATION	\$30,875,000.00 765 \$33,858,500.00		
Acknowledge Addenda (5)	Yes		
Bid Bond	Yes		
Trench Safety Act	Yes		
Bidder Information Form	Yes		
Experience of Bidder	Yes		
Non-Collusion Affidavit	Yes		
Certificate of Nonsegregated Facilities	Yes		
American w/Disabilities Affidavit	Yes		

THE APPARENT LOW BIDDER IS DETERMINED BY THE A + B COMPUTATION

Opened and Tabulated by: T. Roberts, CPPB

Posted: 03/23/2006

Recommendation:

AGREEMENT (CC-0569-06/TLR)

THIS AGREEMENT is dated as of the ____ day of _____ 20____, by and between **HUBBARD CONSTRUCTION CO.**, duly authorized to conduct business in the State of Florida, whose mailing address is P.O. Box 547217, Orlando, Florida 32854, hereinafter called the "CONTRACTOR", and **SEMINOLE COUNTY**, a political subdivision of the State of Florida, whose address is Seminole County Services Building, 1101 East First Street, Sanford, Florida 32771, hereinafter called the "COUNTY". COUNTY and CONTRACTOR, in consideration of the mutual covenants hereinafter set forth, agree as follows:

W I T N E S S E T H:

Section 1. Work. The CONTRACTOR shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as CC-0569-06/TLR - Airport Boulevard Phases II and III.

The Project for which the Work under the Contract Documents is a part is generally described as CC-0569-06/TLR - Airport Boulevard Phases II and III.

Section 2. Engineer.

(a) ENGINEER OF RECORD as named in the Contract Documents for Phase II shall mean PBS&J, 482 S. Keller Road, Orlando, Florida 32810 and the ENGINEER OF RECORD as named in the Contract Documents for Phase III shall mean Inwood Consulting Engineers, 870 Clark Street, Oviedo, Florida 32765.

(b) "CEI" is the Seminole County Engineer or the COUNTY's contracted Consultant for construction, engineering and inspection

("CEI") services. As named in the Contract Documents, "CEI" shall mean PBS&J, 482 S. Keller Road, Orlando, Florida 32810.

Section 3. Contract Time.

(a) All provisions regarding Contract Time are essential to the performance of this Agreement.

(b) The Work shall be substantially completed as described in subsection 14.13 of the General Conditions, within seven hundred sixty (760) calendar days after the date when the Contract Time begins to run as provided in subsection 2.2 of the General Conditions. The Work shall be finally completed, ready for Final Payment in accordance with subsection 14.9 of the General Conditions, within thirty (30) calendar days after the actual date of Substantial Completion.

(c) The parties acknowledge that the Contract Time provided in this Section includes consideration of adverse weather conditions common to Central Florida including the possibility of hurricanes and tropical storms.

(d) The Contract Time provided in this Section includes thirty (30) days allocated specifically to CONTRACTOR's responsibility for utility coordination or relocation of utilities at or adjacent to the Project site. The thirty (30) days shall be depicted by CONTRACTOR as float time not impacting Controlling Work Items on the CONTRACTOR's critical path scheduling. No Contract Time extensions shall be considered related to utility coordination matters including, but not limited to, utility relocations and conflicts unless the utility related time impacts exceed thirty (30) Days impact on Controlling Items of Work in accordance with the Project Schedule.

(e) In the event that the Work requires phased construction, then multiple points of Substantial Completion may be established in the Supplementary Conditions.

Section 4. Contract Price.

(a) COUNTY shall pay CONTRACTOR for performance of the Work in accordance with the Contract Documents on the basis of the Total Bid (original Contract Price.) The CONTRACTOR's total compensation is TWENTY-TWO MILLION NINE HUNDRED SEVENTY-TWO THOUSAND ONE HUNDRED AND 20/100 DOLLARS (\$22,972,100.20) subject only to increases or decreases made in strict conformance with the Contract Documents.

(b) CONTRACTOR agrees to accept the Contract Price as full compensation for doing all Work, furnishing all Materials, and performing all Work embraced in the Contract Documents; for all loss or damage arising out of performance of the Work and from the action of the elements or from any unforeseen or unknown difficulties or obstructions which may arise or be encountered in the prosecution of the Work until the Final Acceptance; and for all risks of every description connected with the Work.

(c) The CONTRACTOR acknowledges that CONTRACTOR studied, considered and included in CONTRACTOR's Total Bid (original Contract Price) all costs of any nature relating to: 1) performance of the Work under Central Florida weather conditions; 2) applicable law, licensing, and permitting requirements; 3) the Project site conditions, including but not limited to, subsurface site conditions; 4) the terms and conditions of the Contract Documents, including, but

not limited to, the indemnification and no damage for delay provisions of the Contract Documents.

(d) The CONTRACTOR acknowledges that performance of the Work will involve significant Work adjacent to, above and in close proximity to Underground Facilities including utilities which will require the support of active utilities, as well as, the scheduling and sequencing of utility installations and relocations (temporary and permanent) by CONTRACTOR.

(1) In addition to the acknowledgments previously made, the CONTRACTOR acknowledges that the CONTRACTOR's Total Bid (original Contract Price) specifically considered and relied upon CONTRACTOR's own study of Underground Facilities, utilities in their present, relocated (temporary and permanent) and proposed locations, and conflicts relating to utilities and Underground Facilities.

(2) The CONTRACTOR acknowledges that CONTRACTOR's Total Bid (original Contract Price) considered and included all of CONTRACTOR's costs relating to CONTRACTOR's responsibilities to coordinate and sequence the Work of the CONTRACTOR with the work of the COUNTY with its own forces, the work of other utility contractors and the work of others at the Project site.

Section 5. Payment Procedures.

(a) CONTRACTOR shall submit Applications for Payment in accordance with Section 14 of the General Conditions. Applications for Payment will be processed by ENGINEER as provided in the General Conditions.

(b) Progress Payments. COUNTY shall make progress payments on the basis of CONTRACTOR's Applications for Payment as recommended by ENGINEER, in accordance with Section 14 of the General Conditions.

(c) Final Payment. Upon Final Completion and acceptance of the Work in accordance with subsection 14.9.1 of the General Conditions, COUNTY shall pay the remainder of the Contract Price as provided in subsection 14.9.1.

Section 6. Additional Retainage For Failure to Maintain Progress on the Work.

(a) Retainage under the Contract Documents is held as collateral security to secure completion of the Work.

(b) In the event that CONTRACTOR fails to physically mobilize to the Work site as required by Section 6.19 of the General Conditions, then the COUNTY may withhold additional retainage to secure completion of the Work in an amount equal to the product of the number of days after the 31st day following the Date of Commencement of Contract Time and the liquidated damage amount for Substantial Completion set forth in Section 9 of this Agreement. The additional retainage shall be withheld from the initial and each subsequent Progress Payment. The additional retainage held under this subsection shall be released to CONTRACTOR in the next Progress Payment following the ENGINEER's approval of a supplementary Progress Schedule demonstrating that the requisite progress will be regained and maintained as required by Section 6.19.2 of the General Conditions.

(c) COUNTY may withhold additional retainage in anticipation of liquidated damages equal to the product of the number of days after

the scheduled Contract Time (Substantial Completion or Final Completion) and the amount of liquidated damages set forth in Section 9 of this Agreement if CONTRACTOR is behind schedule and it is anticipated by COUNTY that the Work will not be completed within the Contract Time. The additional retainage, under this subsection, may at the COUNTY'S discretion be withheld from subsequent Progress Payments. Any additional retainage held under this subsection shall be released to CONTRACTOR in the next Progress Payment following the ENGINEER'S approval of a supplemental Progress Schedule demonstrating that the requisite progress will be regained and maintained as required by Section 6.19.2 of the General Conditions.

Section 7. Contractor's Representations. In order to induce COUNTY to enter into this Agreement, CONTRACTOR makes the following representations:

(a) CONTRACTOR has familiarized himself with the nature and extent of the Contract Documents, Work, locality, weather, Chapter 220, Part 1, "Purchasing Code," Seminole County Code, and with all local conditions and federal, state and local laws, utility locations, ordinances, rules, policies and regulations that in any manner may affect cost, progress or performance of the Work.

(b) CONTRACTOR has studied carefully and considered in its Bid all reports of investigations and tests of subsurface and physical conditions of the site affecting cost, progress, scheduling, or performance of the Work.

(c) CONTRACTOR has studied carefully and considered in its Bid the Plans and Specifications, performed necessary observations,

examinations and studied the physical conditions at the site related to Underground Facilities, utility installations, conflicts, relocations (temporary and permanent) and all other Underground Facilities and utility related conditions of the Work and site that may affect cost, progress, scheduling or any aspect of performance of the Work and that its Bid reflects all such conditions. CONTRACTOR, by submitting its Bid and executing this Agreement acknowledges the constructability of the Work under the Plans and Specifications. CONTRACTOR by its study, excludes and releases the COUNTY from any implied warranties, including but not limited to, the "Spearin Doctrine," that the Plans and Specifications are adequate to perform the Work.

(d) CONTRACTOR has made or caused to be made examinations, investigations and tests and studies as he deems necessary for the performance of the Work at the Contract Price, within the Contract Time and in accordance with the other terms and conditions of the Contract Documents; and no additional examinations, investigations, tests, reports or similar data are or will be required by CONTRACTOR for such purposes.

(e) CONTRACTOR has correlated the results of all such observations, examinations, investigations, tests, reports and data with the terms and conditions of the Contract Documents.

(f) CONTRACTOR has given ENGINEER written notice of all conflicts, errors or discrepancies that he has discovered in the Contract Documents and the written resolution thereof by ENGINEER is acceptable to CONTRACTOR.

(g) The CONTRACTOR declares and agrees that the approval or acceptance of any part of the Work or Material by the COUNTY, ENGINEER or any agent relating to compliance with the Contract Documents shall not operate as a waiver by the COUNTY of strict compliance with the terms and conditions of the Contract Documents.

(h) The CONTRACTOR declares and agrees that the COUNTY may require him to repair, replace, restore or make all things comply with the Contract Documents including all Work or Materials which within a period of two (2) years from Acceptance by COUNTY are found to be Defective or fail in any way to comply with the Contract Documents. The CONTRACTOR acknowledges that the above two (2) years repair, replace and restoration period is separate from and additional to CONTRACTOR's warranty that the Work has been completed in compliance with the Contract Documents. The two (2) years repair, replace and restoration period is not a limitation upon CONTRACTOR's other warranties or Material and Workmanship Bond.

(i) The CONTRACTOR's resident Superintendent at the Work site shall be Ernest J. Wolf and this Superintendent only shall be utilized by the CONTRACTOR unless otherwise approved by the COUNTY Project Manager and following the procedure indicated in the General Conditions.

(j) CONTRACTOR has studied carefully and considered all permit requirements related to performance of the Work. CONTRACTOR declares and agrees that all costs related to performing the Work in compliance with the requirements of all permits at the Contract Price are included in the Contract Price. CONTRACTOR agrees that CONTRACTOR

shall be solely responsible for payment of all fines and penalties of any nature assessed to the CONTRACTOR or COUNTY or both by any governmental entity, district, authority or other jurisdictional entity relating to all permits required for performance of the Work.

(k) CONTRACTOR acknowledges that the performance of the Work under the Contract Documents fulfills a COUNTY, CONTRACTOR and public purpose. To that end, CONTRACTOR agrees to respond to citizen complaints related to alleged damage caused by CONTRACTOR'S performance of the Work within ten (10) days of receipt of the complaint from citizens, ENGINEER or the COUNTY. The CONTRACTOR shall utilize the attached "Report of Unsatisfactory Materials and/or Service" form to respond separately to each complaint. When a complaint is brought to the CONTRACTOR by a citizen, the CONTRACTOR shall identify the citizen and street address in the "Statement of Problem". Responses and action taken by the CONTRACTOR shall specifically identify the problem and specific actions taken. Generic statements such as "addressed the problem" are unacceptable. If the CONTRACTOR fails to respond within ten (10) days, then the COUNTY may take corrective action and deduct the actual costs of corrective action from subsequent Progress Payments or the retainage.

(l) CONTRACTOR acknowledges that the COUNTY owned property obtained for performance of the Work within the project limits includes temporary construction easements. In the event that the CONTRACTOR fails to perform the Work within the Contract Time, then CONTRACTOR shall be solely responsible for payment of all costs for additional or extended temporary construction easements. The

CONTRACTOR authorizes the COUNTY to deduct the actual costs of additional or extended temporary construction easements from subsequent Progress Payments or the retainage.

Section 8. Contract Documents. The Contract Documents which comprise the entire agreement between COUNTY and CONTRACTOR are made a part hereof and consist of the following:

- (a) This Agreement.
- (b) Addenda.
- (c) Bid.
- (d) American With Disabilities Act Affidavit.
- (e) Performance Bond.
- (f) Payment Bond.
- (g) Material and Workmanship Bond.
- (h) Specifications.
- (i) Technical Specifications Provided in these Contract Documents.
- (j) General Conditions.
- (k) Supplementary Conditions including any utility specific forms provided by the COUNTY's Utility Division.
- (l) Notice To Proceed.
- (m) Change Orders.
- (n) Certificate of Substantial Completion.
- (o) Certificate of Final Inspection.
- (p) Certificate of Engineer.
- (q) Certificate of Final Completion.
- (r) CONTRACTOR's Release.
- (s) Drawings and Plans.

- (t) Supplemental Agreements.
- (u) CONTRACTOR's Waiver of Lien (Partial).
- (v) CONTRACTOR's Waiver of Lien (Final and Complete).
- (w) Subcontractor/Vendor's Waiver of Lien (Final and Complete).
- (x) Consent of Surety to Final Payment.
- (y) Instructions to Bidders.
- (z) CONTRACTOR's Insurance Requirements, Certificate and Insurance Policies.

There are no Contract Documents other than those listed above in this Section 8. The Contract Documents may only be altered, amended or repealed by a modification as provided in the General Conditions.

Section 9. Liquidated Damages.

(a) The COUNTY and CONTRACTOR recognize that time is essential to the performance of this Agreement and CONTRACTOR recognizes that the COUNTY and its traveling public will suffer financial loss if the Work is not substantially completed as described in subsection 14.13 of the General Conditions within the time specified below, plus any extensions thereof allowed in accordance with Section 12 of the General Conditions. The parties also recognize the delays, expense and difficulties involved in proving in a legal or alternative dispute resolution proceeding the damages resulting from inconvenience to the traveling public including traffic loading, intersection operations, costs for time, costs of fuel and costs for some environmental impacts (excluding actual delay damages which may include, but are not limited to, engineering fees and inspection costs) suffered by the COUNTY if the Work is not completed on time. Accordingly, CONTRACTOR and

CONTRACTOR's Surety agree to pay COUNTY as liquidated damages, and not as a penalty, THREE THOUSAND NINE HUNDRED AND NO/100 DOLLARS (\$3,900.00) per day for each day exceeds the Bidder's Contract Time ("B" of the A+B Bid) for Substantial Completion until the Work is Substantially Complete. Additionally, liquidated damages of ONE THOUSAND THREE HUNDRED AND NO/100 DOLLARS (\$1,300.00) per day shall be assessed for each day beyond one hundred twenty (120) days from issuance of the Notice to Proceed that it takes CONTRACTOR to complete the construction of Pond A and all associated drainage structures along S.R. 46A and Airport Boulevard in their entirety as defined in the Contract Documents. It is agreed that if this Work is not Finally Completed in accordance with the Contract Documents, the CONTRACTOR shall pay the COUNTY as liquidated damages for delay, and not as a penalty, one-fourth (1/4) of the rate set forth above.

(b) The CONTRACTOR shall pay or reimburse, in addition to the liquidated damages specified herein, the COUNTY's actual damages which may include, but are not limited to, expenses for engineering fees and inspection costs arising from CONTRACTOR's failure in meeting either or both the Substantial Completion and Final Completion dates.

(c) The liquidated damages provided in this Section are intended to apply even if CONTRACTOR is terminated, in default or if the CONTRACTOR has abandoned the Work.

Section 10. Miscellaneous.

(a) Terms used in this Agreement which are defined in Section 1 of the General Conditions shall have the meanings indicated in the General Conditions.

(b) No assignments by a party hereto of any rights under or interests in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound and any such assignment shall be void and of no effect; and specifically, but without limitation, monies that may become due and monies that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law); and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.

(c) COUNTY and CONTRACTOR each binds himself, his partners, successors, assigns and legal representatives to the other party hereto, his partners, successors, assigns and legal representatives in respect to all covenants, agreements and obligations contained in the Contract Documents.

Section 11. Contractor's Specific Consideration. In consideration of the CONTRACTOR's indemnity agreements as set out in the Contract Documents, COUNTY specifically agrees to pay the CONTRACTOR the sum of TWO HUNDRED FIFTY AND NO/100 DOLLARS (\$250.00). The CONTRACTOR acknowledges receipt of the specific consideration for CONTRACTOR's indemnification of COUNTY and that the specific consideration is included in the original Contract Price allocated by CONTRACTOR among all pay items - receipt of which is acknowledged.

Section 12. Notices. Whenever either party desires to give notice unto the other including, but not limited to, Contract Claims, it must be given by written notice, hand delivered, signed and dated

for receipt or sent by certified United States mail, with return receipt requested, addressed to the party for whom it is intended at the place last specified and the place for giving of notice shall remain such until it shall have been changed by written notice in compliance with the provisions of this Section. For the present, the parties designate the following as the respective places for giving of notice, to wit:

For COUNTY:

Engineering Division
520 W. Lake Mary Boulevard, Suite 200
Sanford, FL 32773

For CONTRACTOR:

Hubbard Construction Co.
Attn: Ernest J. Wolf
P.O. Box 547217
Orlando, FL 32854

Section 13. Conflict of Interest.

(a) The CONTRACTOR agrees that it will not engage in any action that would create a conflict of interest in the performance of its obligations pursuant to this Agreement with the COUNTY or which would violate or cause others to violate the provisions of *Part III, Chapter 112, Florida Statutes*, relating to ethics in government. See County Personnel Policy 4.10(F).

(b) The CONTRACTOR hereby certifies that no officer, agent or employee of the COUNTY has any material interest (as defined in *Section 112.312 (15), Florida Statutes*, as over 5%) either directly or indirectly, in the business of the CONTRACTOR to be conducted here and that no such person shall have any such interest at any time during the term of this Agreement.

(c) Pursuant to Section 216.347, Florida Statutes, the CONTRACTOR hereby agrees that monies received from the COUNTY pursuant to this Agreement will not be used for the purpose of lobbying the Legislature or any other State or Federal Agency.

Section 14. Material Breaches of Agreement.

(a) The parties recognize that breaches of the Contract Documents may occur and that remedies for those breaches may be pursued under the Contract Documents. The parties further recognize that the safety of the traveling public is of paramount concern. Therefore, the parties agree that any breach of the Contract Documents related to life safety, including but not limited to, the maintenance of traffic requirements of the Contract Documents, shall be considered a breach of the Contract Documents.

(b) Upon a material breach of the Contract Documents related to life safety, as determined by ENGINEER, the ENGINEER shall issue a Stop Work Order suspending the Work or any specific portion of the Work until the conditions are corrected. If the life safety conditions giving rise to the Stop Work Order are not corrected within a reasonable time, as determined by ENGINEER, then the material breach shall entitle COUNTY to terminate this Agreement. The recognition of breaches of the provisions of the Contract Documents related to life safety as material breaches shall not be construed as a limitation on other remedies for breaches or material breaches of the Contract Documents.

IN WITNESS WHEREOF, the parties hereto have signed this Agreement. All portions of the Contract Documents have been signed or identified by COUNTY and CONTRACTOR or by ENGINEER on their behalf.

ATTEST:

HUBBARD CONSTRUCTION CO.

Secretary

By: _____
JEAN-NOEL KELLY, Vice-President

(CORPORATE SEAL)

Date: _____

ATTEST:

BOARD OF COUNTY COMMISSIONERS
SEMINOLE COUNTY, FLORIDA

MARYANNE MORSE
Clerk to the Board of
County Commissioners of
Seminole County, Florida.

By: _____
CARLTON HENLEY, Chairman

Date: _____

For the use and reliance
of Seminole County only.

Approved as to form and
legal sufficiency.

As authorized for execution
by the Board of County Commissioners
at their _____, 20____
regular meeting.

County Attorney

AC/lpk
3/28/06
cc-0569

**BID FORM
(A+B BID)**

**SEMINOLE COUNTY, FLORIDA
FOR THE CONSTRUCTION OF**

PROJECT: **AIRPORT BOULEVARD PHASE II & III**

COUNTY CONTRACT NO. **CC-0569-06/TLR**

Name of Bidder: HUBBARD CONSTRUCTION COMPANY

Mailing Address: P0 Box 547217, Orlando, FL 32854

Street Address: 1936 Lee Road

City/State/Zip: Winter Park, FL 32789

Phone Number: (407) 645-5500

FAX Number: (407) 623-3865

Contractor License Number: CGC 1508130

Exhibit "A"

The Bidder shall be FDOT prequalified for this type of Work.

TO: Purchasing Division of Seminole County, Florida

Pursuant to and in compliance with your notice inviting sealed Bids (Invitation for Bid), Instructions to Bidders, and the other documents relating thereto, the undersigned Bidder, having familiarized himself with the terms of the Contract Documents, local conditions affecting the performance of the Work, and the cost of the Work at the place where the Work is to be done, hereby proposes and agrees to perform within the time stipulated in the Contract Documents, including all of its component parts and everything required to be performed, and to provide and furnish any and all of the labor, Material, and tools, expendable Equipment, and all utility and transportation services necessary to perform the Work and complete in a workmanlike manner, all of the Work required in connection with the construction of said Work all in strict conformity with the Plans and Specifications and other Contract Documents, including Addenda Nos. 1 through 5, on file at the Purchasing Division for the Total Bid (Contract Price) hereinafter set forth.

The undersigned Bidder agrees that the Work shall be completed according to the schedule set forth in the Contract Documents.

The undersigned Bidder further agrees to pay liquidated damages as described in the Contract Documents.

Bid prices must be stated in words in accordance with these Instructions to Bidders in the blank space(s) provided for that purpose.

Bidder acknowledges that it has read and fully understands all Sections of the Instructions To Bidders.

The undersigned, as Bidder, declares that the only persons or parties interested in this proposal as principals are those named herein; that this proposal is made without collusion with any person, firm or corporation; and he proposes and agrees, if the proposal is accepted, that he will execute an Agreement with the COUNTY in the form set forth in the Contract Documents; that he will furnish the Contract Security, Insurance Certificates, Endorsements, and Policies, that he is aware that failure to properly comply with the requirements set out in the "Instructions to Bidders" and elsewhere in the Contract Documents may result in a finding that the Bidder is non-responsive and may cause a forfeiture of the Bid Security.

Attention: Bids shall only be considered from those Bidders who have obtained these Contract Documents directly from the COUNTY by purchase.

**BID FORM
(A+B BID)**

PROJECT: **AIRPORT BOULEVARD PHASE II& III**

COUNTY CONTRACT NO. **CC-0569-06/TLR**

TO: Board of County Commissioners
 Seminole County, Florida

Pursuant to and in compliance with the Instructions to Bidders, the undersigned computes the A+B computation as follows:

- (a) The COUNTY specifies the maximum Contract Time for Final Completion as 765 Days.
- (b) The COUNTY specifies the RUC as \$3,900 per Day.
- (c) A+B computation = A + (B x RUC)

Where:

A = Bidder's Total Bid \$ 22,972,100.20

B = Bidder's Contract Time 760 Days.

(must be less than the maximum Contract Time and more than the minimum Contract Time provided by the COUNTY)

A+B COMPUTATION : 25,936,100.20

Twenty five million, nine hundred ^{Numbers} thirty six thousand, one hundred dollars
and twenty cents

(IN WORDS)

(A+B computation is used only to determine the Apparent Low Bidder).

- (d) The Total Amount of Bid stated below must be the same as "A" Bidder's Total Bid as set forth in the Bidder's A+B Bid formula. This sum shall be the Contract Price if a contract is awarded.
- (e) The Bidder's Contract Time is the same as "B" Bidder's Contract Time as set forth in the Bidder's A+B Bid formula. The number of Days stated in the Bidder's A+B Bid formula shall be the Contract Time.

Pursuant to and in compliance with your Invitation for Bid, the Instructions to Bidders, and other documents relating thereto, the undersigned hereby agrees to furnish all labor, Materials and Equipment to do the Work in strict accordance with the Contract Documents and all addenda, if any, issued prior to the date of this Bid at the Total Bid herein as follows:

TOTAL AMOUNT OF BID: \$22,972,100.20

(Must equal "A" in the Bidder's A+B formula)

Numbers

Twenty two million, nine hundred seventy two thousand, one hundred dollars and
twenty cents

(IN WORDS)

CONTRACT TIME: 760 days

(Must equal "B" in the Bidder's A+B formula)

Number of Days

Seven Hundred Sixty Days

(IN WORDS)

1. The Bidder acknowledges that the Total Amount of Bid stated above includes the sum of \$250.00, specific consideration for indemnification.
2. The Bidder acknowledges that the Total Amount of Bid stated above includes compensation for all Work, labor, permits, bonds, equipment, materials, and any and all incidental costs necessary for the proper execution of the required services.

The Bidder acknowledges the receipt, execution, and return of the following forms:

Section 00100 - Bid Forms, including alternates and addendum, if any.
Section 00150 - Trench Safety Act Form
Section 00160 - Bidder Information Forms (including W-9 form)
Section 00300 - Non-Collusion Affidavit of Bidder Form
Section 00310 - Certification of Nonsegregated Facilities Form
Section 00630 - Americans with Disabilities Act Form

IN WITNESS WHEREOF, BIDDER has hereunto executed this BID FORM this 22nd day
of March, 2006.

HUBBARD CONSTRUCTION COMPANY
(Name of BIDDER)

(Signature of person signing this BID FORM)

Jean-Noel Kelly

(Printed name of person signing this BID FORM)

Senior Vice President - Construction Operations
(Title of person signing this BID FORM)

ACCOMPANYING THIS BID IS Bidder's Bond

(insert the word(s) "cashier's check," bidder's bond," certified check," or other security as provided by
law, as the case may be) in an amount equal to at least five percent (5%) of the Total Bid, payable to the

BOARD OF COUNTY COMMISSIONERS, SEMINOLE COUNTY, FLORIDA

The undersigned deposits above-named security as a Bid guarantee and agrees that it shall be
forfeited to the COUNTY as liquidated damages in case this Bid is accepted by the COUNTY and the
undersigned fails to execute an Agreement with the COUNTY as specified in the Contract Documents
accompanied by the required Payment and faithful Performance Bonds with Sureties satisfactory to the
COUNTY, and accompanied by the required certificates of insurance coverage, and endorsements.
Should the COUNTY be required to engage the services of an attorney in connection with the
enforcement of this Bid, Bidder promises to pay COUNTY's reasonable attorney's fees and costs
(including attorney's fees and costs on appeals) incurred with or without suit.

**BID FORM
(A+B BID)**

PROJECT: **AIRPORT BOULEVARD PHASE II & III**

COUNTY CONTRACT NO. **CC-0569-06/TLR**

SEMINOLE COUNTY

ROADWAY PAY ITEMS	TOTAL \$ <u>20,997,282.80</u>
SIGNING AND MARKING PAY ITEMS	TOTAL \$ <u>116,172.40</u>
SIGNALIZATION PAY ITEMS	TOTAL \$ <u>1,243,195.00</u>
ENVIRONMENTAL REMEDIATION PAY ITEMS	TOTAL \$ <u>615,450.00</u>

A = BIDDERS TOTAL BID **BID TOTAL \$ 22,972,100.20**
BIDDER TOTAL TO BE ENTERED ON PAGE 00100-4
FOR COMPUTATION

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
101-1	LS	MOBILIZATION		1	1	2,200,000.00 2,200,000.00	2,200,000.00
104-1	SY	ARTIFICIAL COVERINGS		2,653	2,653	1.00	2,653.00
104-4	AC	MOWING	39.0	27.4	66.4	100.00	6,640.00
104-10-1	TN	BALED HAY OR STRAW	4,480	2,116	6,596	6.00	39,576.00
104-12	LF	STAKED TURBIDITY BARRIER	3,172	360	3,532	4.00	14,128.00
104-13-1	LF	STAKED SILT FENCE (TYPE III)	3,744	24,595	28,339	1.00	28,339.00
110-1-1	LS	CLEARING AND GRUBBING		1	1	2,000,000.00	2,000,000.00
110-4	SY	REMOVAL OF EXIST CONCRETE PAVEMENT	1,205	6,073	7,278	5.00	36,390.00
110-7-1	EA	MAILBOX (FURNISH AND INSTALL)		17	17	200.00	3,400.00
120-1-	CY	REGULAR EXCAVATION	19,699	171,192	190,891	15.00	2,863,365.00
120-4-	CY	SUBSOIL EXCAVATION	3,752	3,585	7,337	15.00	110,055.00
120-6-	CY	EMBANKMENT	45,992		45,992		
		Deleted Addenda #5					
160-4	SY	TYPE B STABILIZATION (12")	67,592	110,262	177,854	2.50	444,635.00
285-706	SY	OPTIONAL BASE (BASE GROUP 6)		1,427	1,427	15.00	21,405.00
285-707	SY	OPTIONAL BASE (BASE GROUP 7)		3,766	3,766	15.00	56,490.00
285-709	SY	OPTIONAL BASE (BASE GROUP 9)	54,975	74,752	129,727	15.00	1,945,905.00
300-1-3	GA	BITUMINOUS MATERIAL (TACK COAT)	4,495		4,495	2.00	8,990.00
327-70-1	SY	MILLING EXISTING ASPHALT PAVEMENT (1" AVG DEPTH)	2,016		2,016	9.00	18,144.00
331-72-10	SY	TYPE S ASPHALTIC CONCRETE (INC BIT) (1")		1,427	1,427	8.00	11,416.00
331-72-20	SY	TYPE S ASPHALTIC CONCRETE (INC BIT) (2")		3,766	3,766	14.00	52,724.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
331-72-30	SY	TYPE S ASPHALTIC CONCRETE (INC BIT) (3")	54,926	74,752	129,678	16.00	2,074,848.00
337-5-3	SY	ASPHALTIC CONCRETE FRICTION COURSE (RUBBER) (1") (FC-3)	56,942	80,555	137,497	7.00	962,479.00
339-1-	TN	MISCELLANEOUS ASPHALT PAVEMENT		104	104	100.00	10,400.00
400-1-2	CY	CLASS I CONCRETE (END WALLS)		47.7	48	1,500.00	72,000.00
400-1-11	CY	CLASS I CONCRETE (GRAVITY WALLS)		32.4	32.4	750.00	24,300.00
400-1-15	CY	CLASS I CONCRETE (MISCELLANEOUS CONTINGENT)	21.5	5.0	26.5	700.00	18,550.00
400-2-1	CY	CLASS II CONCRETE (CULVERTS)		0.7	0.7	2,000.00	1,400.00
400-4-1	CY	CLASS IV CONCRETE (CULVERTS)		1,184.30	1,184.30	850.00	1,006,655.00
415-1-1	LB	REINFORCING STEEL (ROADWAY)		177,421	177,421	.80	141,936.80
425-1-311	EA	INLET (CURB TYPE P-1) (<10')	5		5	4,500.00	22,500.00
425-1-321	EA	INLET (CURB TYPE P-2) (<10')	4		4	5,000.00	20,000.00
425-1-351	EA	INLET (CURB TYPE P-5) (<10')	19	54	73	4,500.00	328,500.00
425-1-361	EA	INLET (CURB TYPE P-6) (<10')	10	20	30	4,500.00	135,000.00
425-1-451	EA	INLET (CURB TYPE J-5) (<10')	6	8	14	8,000.00	112,000.00
425-1-452	EA	INLET (CURB TYPE J-5) (>10')	3	1	4	8,000.00	32,000.00
425-1-461	EA	INLET (CURB TYPE J-6) (<10')	3	6	9	8,000.00	72,000.00
425-1-462	EA	INLET (CURB TYPE J-6) (>10')	1		1	8,000.00	8,000.00
425-1-471	EA	INLET (CURB TYPE P-7) (<10')	8		8	4,500.00	36,000.00
425-1-473	EA	INLET (CURB TYPE J-7, J-BOTTOM) (<10')	1		1	8,000.00	8,000.00
425-1-521	EA	INLET (DT BOT TYPE C) (<10')		3	3	4,000.00	12,000.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
425-1-541	EA	INLET (DT BOT TYPE D) (<10')	1	6	7	7,000.00	49,000.00
425-1-551	EA	INLET (DT BOT TYPE E) (<10')		1	1	6,000.00	6,000.00
425-1-581	EA	INLET (DT BOT TYPE H) (<10')		1	1	7,000.00	7,000.00
425-2-41	EA	MANHOLE (P-7) (<10')	9		9	4,000.00	36,000.00
425-2-42	EA	MANHOLE (P-7) (>10')	1		1	4,000.00	4,000.00
425-2-61	EA	MANHOLE (P-8) (<10')		8	8	4,000.00	32,000.00
425-2-63	EA	MANHOLE (P-8) (PARTIAL)		5	5	3,500.00 3,500.00	17,500.00
425-2-71	EA	MANHOLE (J-7) (<10')	12		12	6,000.00	72,000.00
425-2-72	EA	MANHOLE (J-7) (>10')	4		4	6,500.00	26,000.00
425-2-91	EA	MANHOLE (J-8) (<10')		11	11	13,000.00	143,000.00
425-2-92	EA	MANHOLE (J-8) (>10')		4	4	12,500.00	50,000.00
425-4-	EA	ADJUSTING INLETS		1	1	3,000.00	3,000.00
425-10-	EA	YARD DRAINS (CONTINGENT)		10	10	800.00	8,000.00
430-171-123	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (15")	6		6	250.00	1,500.00
430-171-125	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (18")	3,347	6,631	9,978	60.00	598,680.00
430-171-129	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (24")	2,369	2,539	4,908	70.00	343,560.00
430-171-133	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (30")	2,246	3,268	5,514	90.00	496,260.00
430-171-138	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (36")	1,396	1,166	2,562	120.00	307,440.00
430-171-140	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (42")		275	275	150.00	41,250.00
430-171-141	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (48")	830	14	844	180.00	151,920.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
430-171-142	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (54")		608	608	200.00	121,600.00
430-171-143	LF	CONCRETE PIPE CULVERT (STORM SEWER) (CLASS III) (60")		198	198	230.00	45,540.00
430-171-225	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (14" X 23")	133		133	70.00	9,310.00
430-171-229	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (19" X 30")	96		96	80.00	7,680.00
430-171-233	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (24" X 36")	232	166	398	120.00	47,760.00
430-171-238	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (29" X 45")		418	418	130.00	54,340.00
430-171-241	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (38" X 60")	103	464	567	180.00	102,060.00
430-171-242	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (43" X 68")		102	102	250.00	25,500.00
430-171-243	LF	ELLIPTICAL CONC PIPE CULV (SS) (HE III) (48" X 76")		1,183	1,183	250.00	295,750.00
430-880-29	EA	FLAP GATE (24")		1	1	7,500.00 7,500.00	7,500.00
430-880-33	EA	FLAP GATE (30")		1	1	10,000.00 10,000.00	10,000.00
430-982-123	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (15")	2		2	800.00	1,600.00
430-982-125	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (18")	3		3	1,000.00	3,000.00
430-982-225	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (18")		4	4	1,100.00	4,400.00
430-982-233	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (30")		4	4	2,000.00	8,000.00
430-982-238	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (36")		2	2	2,500.00	5,000.00
430-982-240	EA	MITERED END SECTION (CD) (CONCRETE PIPE ROUND) (42")		2	2	3,000.00	6,000.00
430-982-404	EA	MITERED END SECTION (CD) (CONCRETE ELLIP PIPE) (24" X 38")		1	1	2,000.00	2,000.00
430-982-409	EA	MITERED END SECTION (CD) (CONCRETE ELLIP PIPE) (38" X 60")		4	4	4,000.00	16,000.00
430-982-625	EA	MITERED END SECTION (CD) (CONCRETE ELLIPTICAL ARCH) (18")	2		2	1,200.00	2,400.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
430-984-225	EA	MITERED END SECTION (SD) (CONCRETE PIPE ROUND) (18")		3	3	1,000.00	3,000.00
430-984-229	EA	MITERED END SECTION (SD) (CONCRETE PIPE ROUND) (24")		1	1	1,200.00	1,200.00
430-984-238	EA	MITERED END SECTION (SD) (CONCRETE PIPE ROUND) (36")		2	2	2,400.00	4,800.00
440-1-10	LF	UNDERDRAIN, TYPE I (6")	2,159	8,036	10,195	22.00	224,290.00
514-71-3	SY	PLASTIC FILTER FABRIC	70		70	24.00	1,680.00
515-2-301	LF	PEDESTRIAN/BICYCLE RAILING (ALUMINUM) (PICKET 42")	52	280	332	45.00	14,940.00
520-1-7	LF	CONCRETE CURB & GUTTER (TYPE E)	7,513	15,944	23,457	15.00	351,855.00
520-1-10	LF	CONCRETE CURB & GUTTER (TYPE F)	14,258	27,167	41,425	15.00	621,375.00
520-2-4	LF	CONCRETE CURB, TYPE D	22		22	20.00	440.00
520-3-	LF	CONCRETE VALLEY GUTTER	578	211	789	18.00	14,202.00
520-5-11	LF	CONCRETE TRAFFIC SEPARATOR (TYPE I) (4' WIDE)	176		176	25.00	4,400.00
520-5-16	LF	CONCRETE TRAFFIC SEPARATOR (TYPE I) (8.5' WIDE)	2,557		2,557	34.00	86,938.00
520-5-41	LF	CONCRETE TRAFFIC SEPARATOR (TYPE IV) (4' WIDE)		883	883	26.00	22,958.00
520-70	SY	CONCRETE TRAFFIC SEPARATOR (SPECIAL)	466		466	32.00	14,912.00
522-1	SY	CONCRETE SIDEWALK (4")	3,822	7,861	11,683	30.00	350,490.00
522-2	SY	CONCRETE SIDEWALK (6")	230	2,025	2,255	36.00	81,180.00
524-1-1	SY	CONCRETE DITCH PAVEMENT (NON-REINFORCED) (3") (CONTINGENT)		10	10	55.00	550.00
527-1-2	SF	DETECTABLE WARNING SURFACES AVG 10SF PREFORMED THERMOPLASTIC	290	260	550	50.00	27,500.00
530-1-	CY	RIPRAP (SAND CEMENT)		423.7	423.7	450.00	190,665.00
530-3-4	TN	RIPRAP	50.7		50.7	80.00	4,056.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
ROADWAY PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
536-1-1	LF	GUARDRAIL (ROADWAY)		1,750	1,750	25.00	43,750.00
536-2	LF	GUARDRAIL (SHOP BENT PANELS)		60	60	26.00	1,560.00
536-7	EA	GUARDRAIL POSTS, SPECIAL		4	4	130.00	520.00
536-85-22	EA	END ANCHORAGE ASSEMBLY, FLARED		8	8	800.00	6,400.00
536-85-25	EA	END ANCHORAGE ASSEMBLY, TYPE II		9	9	900.00	8,100.00
536-85-26	EA	END ANCHORAGE ASSEMBLY, TYPE CRT		1	1	2,000.00	2,000.00
547-70-1	SY	FABRIC FORMED CONCRETE RIPRAP (8" FILTER POINTS)	61		61	35.00	2,135.00
550-10-222	LF	FENCE TYPE B (6' HEIGHT) (VINYL COATING)	1,613	558	2,171	12.00	26,052.00
550-10-228	LF	FENCE TYPE B (6' HEIGHT) (RESET EXISTING)		1,971	1,971	5.00	9,855.00
550-60-224	EA	FENCE GATES TYPE B (DOUBLE 10')		1	1	800.00	800.00
550-60-234	EA	SLIDING GATE (CANTILEVER) (20')	2		2	1,800.00	3,600.00
570-5-	TN	FERTILIZER	4.4	13.7	18.1	200.00	3,620.00
570-9-	MG	WATER FOR GRASSING	292	164	456	10.00	4,560.00
575-1-3	SY	SODDING (ARGENTINA BAHIA)	47,150	26,534	73,684	1.50	110,526.00
666-03	LS	RIGHT-OF-WAY SURVEY		1	1	50,000.00	50,000.00
999-01	LS	MAINTENANCE OF TRAFFIC		1	1	500,000.00	500,000.00
999-03	LS	FIELD OFFICE		1	1	70,000.00	70,000.00
		TOTAL ROADWAY	20,997,282.80				

* Not an FDOT Pay Item No.

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
SIGNING AND PAVEMENT MARKING PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
700-40-1	AS	SIGN (SINGLE POST) (LESS THAN 12)	61	66	127	250.00	31,750.00
700-40-2	AS	SIGN (SINGLE POST) (12-25)	1	10	11	350.00	3,850.00
700-46-11	AS	SIGN EXISTING (REMOVE) (SINGLE POST)	29	28	57	32.00	1,824.00
700-46-21	AS	SIGN EXISTING (RELOCATE) (SINGLE POST)	11	3	14	78.00	1,092.00
705-10-11	AS	OBJECT MARKER (POST MOUNTED) (TYPE I)		23	23	130.00	2,990.00
706-3	EA	REFLECTIVE PAVEMENT MARKER, BI-DIRECTIONAL	618	975	1,593	4.00	6,372.00
710-30	EA	REFLECTIVE PAINT (ISLAND NOSE)		50	50	12.00	600.00
711-3	EA	PAVEMENT MESSAGES, THERMOPLASTIC	20	26	46	150.00	6,900.00
711-4	EA	DIRECTIONAL ARROWS, THERMOPLASTIC	48	86	134	45.00	6,030.00
711-31	GM	SKIP TRAFFIC STRIPE, THERMOPLASTIC (6" WHITE)		3,681	3,681	800.00	2,944.80
711-33	LF	SKIP TRAFFIC STRIPE, THERMOPLASTIC (6" WHITE) (10'-30')	3,350		3,350	1.00	3,350.00
711-34	LF	SKIP TRAFFIC STRIPE, THERMOPLASTIC (6" YELLOW)		511	511	1.00	511.00
711-35-81	LF	SOLID TRAFFIC STRIPE (THERMO)(8" WHITE)	325	1,428	1,753	1.00	1,753.00
711-35-121	LF	SOLID TRAFFIC STRIPE (THERMO)(12" WHITE)	1,752	3,670	5,422	2.00	10,844.00
711-35-181	LF	SOLID TRAFFIC STRIPE (THERMO)(18" WHITE)		331	331	2.00	662.00
711-35-241	LF	SOLID TRAFFIC STRIPE (THERMO)(24" WHITE)	665	645	1,310	3.00	3,930.00
711-36-181	LF	SOLID TRAFFIC STRIPE (THERMO) (18" YELLOW)		299	299	2.00	598.00
711-37-61	NM	SOLID TRAFFIC STRIPE (THERMO) (6" WHITE)	3,589	5,472	9,061	1,800.00	16,309.80
711-38-61	NM	SOLID TRAFFIC STRIPE (THERMO) (6" YELLOW)	2,820	4,881	7,701	1,800.00	13,861.80
		TOTAL SIGNING AND PAVEMENT MARKING	116,172.40				

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
SIGNALIZATION PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
555-1-1	LF	CONDUIT, DIRECTIONAL BORE	180		180	18.00	3,240.00
630-1-12	LF	CONDUIT (F&I) (UNDERGROUND)	12,865	12,972	25,837	5.00	129,185.00
630-1-13	LF	CONDUIT (F&I) (UNDER PAVEMENT)	1,940	383	2,323	25.00	58,075.00
630-1-14	LF	CONDUIT (F&I) (UNDERGROUND - JACKED)	160		160	18.00	2,880.00
632-7-1	PI	CABLE (SIGNAL) (F&I)	3	3	6	4,000.00	24,000.00
635-1-11	EA	PULL AND JUNCTION BOXES (F&I) (PULL BOX)	60	108	168	300.00	50,400.00
635-1-15	EA	FIBER OPTIC PULL BOXES	33		33	1,600.00	52,800.00
639-1-11	AS	ELECTRICAL POWER SERVICE (OVERHEAD)		2	2	1,000.00	2,000.00
639-1-21	AS	ELECTRICAL POWER SERVICE (UNDERGROUND)(FURNISHED BY POWER COMPANY)		1	1	3,000.00	3,000.00
639-1-22	AS	ELECTRICAL POWER SERVICE (UNDERGROUND) (PURCHASED BY CONTRACTOR)	2		2	2,000.00	4,000.00
639-2-1	LF	ELECTRICAL SERVICE WIRE (F&I)	195	60	255	1.00	255.00
648-15-40	EA	STEEL MAST ARM, SINGLE ARM, 40' LONG W/ LUMINAIRE ATTACHMENT	2		2	20,000.00	40,000.00
648-15-44	EA	STEEL MAST ARM, SINGLE ARM, 44' LONG W/ LUMINAIRE ATTACHMENT	1		1	20,000.00	20,000.00
648-15-46	EA	STEEL MAST ARM, SINGLE ARM, 46' LONG W/ LUMINAIRE ATTACHMENT	3		3	20,000.00	60,000.00
648-15-50	EA	STEEL MAST ARM, SINGLE ARM, 50' LONG W/ LUMINAIRE ATTACHMENT	2		2	20,000.00	40,000.00
648-15-58	EA	STEEL MAST ARM, SINGLE ARM, 58' LONG W/ LUMINAIRE ATTACHMENT	1		1	25,000.00	25,000.00
648-15-60	EA	STEEL MAST ARM, SINGLE ARM, 60' LONG W/ LUMINAIRE ATTACHMENT	1		1	22,000.00	22,000.00
648-15-70	EA	STEEL MAST ARM, SINGLE ARM, 70' LONG W/ LUMINAIRE ATTACHMENT	1		1	25,000.00	25,000.00
649-415-003	EA	MAST ARMS ASSEMBLY (F&I)		10	10	25,000.00	250,000.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
SIGNALIZATION PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
650-51-311	AS	TRAFFIC SIGNAL, 12" STD (F&I) (3 SECTION 1 WAY)	14	30	44	800.00	35,200.00
650-51-511	AS	TRAFFIC SIGNAL, 12" STD (F&I) (5 SECTION CLUSTER)	10	4	14	1,200.00	16,800.00
653-112	AS	PEDESTRIAN SIGNALS (F&I) (12" INCANDESCENT) (2 WAY)		8	8	800.00	6,400.00
653-181	AS	PEDESTRIAN SIGNAL (F&I) (LED) (1 WAY)	18		18	500.00	9,000.00
653-182	AS	PEDESTRIAN SIGNAL (F&I) (LED) (2 WAY)	2		2	1,000.00	2,000.00
659-101	EA	SIGNAL HEAD AUXILIARIES (F&I) (BACK PLATES, 3 SECTION)	6		6	100.00	600.00
659-106	EA	TUNNEL VISOR (F&I)		110	110	1.00	110.00
659-108	EA	SIGNAL HEAD AUXILIARIES (F&I) (STEEL PEDESTAL)	2		2	1,000.00	2,000.00
659-109	EA	SIGNAL HEAD AUXILIARIES (F&I) (CONCRETE PEDESTAL)	2		2	600.00	1,200.00
659-118	EA	SIGNAL HEAD AUXILIARIES (F&I) (BACK PLATES, 5 SECTION CLUSTER)	4		4	200.00	800.00
660-1-101	EA	INDUCTIVE LOOP DETECTOR (F&I) (TYPE 1)	29		29	200.00	5,800.00
660-1-102	EA	INDUCTIVE LOOP DETECTOR (F&I) (TYPE 2)	10		10	200.00	2,000.00
660-1-109	EA	INDUCTIVE LOOP DETECTOR (F&I) (TYPE 9)		22	22	200.00	4,400.00
660-1-110	EA	INDUCTIVE LOOP DETECTOR (F&I) (TYPE 10)		10	10	200.00	2,000.00
660-2-102	AS	LOOP ASSEMBLY (F&I) (TYPE B)	24	32	56	600.00	33,600.00
660-2-106	AS	LOOP ASSEMBLY (F&I) (TYPE F) (40' MODIFIED)	15	27	42	600.00	25,200.00
661-70-112	AS	PIEZO AXEL SENSOR (F&I)		2	2	1,000.00	2,000.00
665-11	EA	PEDESTRIAN DETECTOR (F&I) (POLE OR C.C. MOUNTED)	20	16	36	100.00	3,600.00
668-15	EA	DETECTOR CABINET (F&I) (TYPE V)		1	1	3,000.00	3,000.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
SIGNALIZATION PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
670-5-112	AS	ACTUATED S.S. CONTROLLER ASSEMBLY (F&I)	2		2	12,000.00	24,000.00
670-5-132	AS	ACTUATED S.S. CONTROLLER ASSEMBLY (F&I) (D-4-4)		3	3	12,000.00	36,000.00
684-14	EA	SYSTEM COMMUNICATIONS (F&I) (FIBER OPTIC CABLE)	10,195	9,681	19,876	6.00	119,256.00
685-102	EA	SYSTEM AUXILIARIES (F&I) (TRANSCEIVER MODULE)		3	3	3,000.00	9,000.00
685-128	EA	SYSTEM AUXILIARIES (F&I) (INTERFACE PANEL)		3	3	500.00	1,500.00
690-10	EA	REMOVE TRAFFIC SIGNAL HEAD ASSEMBLY	20	16	36	25.00	900.00
690-20	EA	REMOVE SIGNAL PEDESTRIAN ASSEMBLY	2		2	25.00	50.00
690-31	EA	REMOVE SIGNAL PEDESTAL	2		2	150.00	300.00
690-33-1	LF	POLE REMOVAL (DEEP) (DIRECT BURIAL)	60	4	64	130.00 130.00	8,320.00
690-50	EA	REMOVE CONTROLLER ASSEMBLY	2	2	4	500.00	2,000.00
690-70	EA	REMOVE DETECTOR PEDESTRIAN ASSEMBLY	2		2	12.00	24.00
690-80	EA	REMOVE SPAN WIRE ASSEMBLY	3	2	5	300.00	1,500.00
690-90	PI	REMOVE CABLING AND CONDUIT	3	2	5	300.00	1,500.00
690-100	PI	REMOVE MISCELLANEOUS SIGNAL EQUIPMENT	3	2	5	500.00	2,500.00
699-1-1	EA	INTERNALLY ILLUMINATED SIGN (F&I) (STREET NAME)	11		11	1,200.00	13,200.00
700-48-1	EA	SIGN PANEL (F&I)	1		1	400.00	400.00
700-89-1	EA	SIGN ELECTRICALLY POWERED (INTERNALLY ILLUMINATED)		12	12	1,200.00	14,400.00
700-89-3	EA	ELECTRIC POWERED SIGN (CHANGEABLE MESSAGE - FIBER OPTICS)	1		1	1,500.00	1,500.00
715-2-138	LF	LIGHTING CONDUIT (F&I-UNDERGROUND) (RGS) (6")	95		95	100.00	9,500.00

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
SIGNALIZATION PAY ITEMS**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
741-70-111	EA	TRAFFIC MONITORING SITE,VEHICLE SENSOR (F&I) (TYPE I) (HALF LANE WIDTH)	13		13	800.00	10,400.00
745-70-12	AS	TRAFFIC MONITORING SITE,INDUCTIVE LOOP ASSEMBLY (F&I) (2)	13		13	800.00	10,400.00
746-71-212	EA	TRAFFIC MONITORING SITE, CABINET (F&I) (BASE) (2)	3		3	3,000.00	9,000.00
		TOTAL SIGNALIZATION	1,243,195.00				

**AIRPORT BOULEVARD - PHASE II & PHASE III
SEMINOLE COUNTY
CONTAMINATED SOIL AND GROUNDWATER REMEDIATION**

ITEM	UNIT	ITEM DESCRIPTION	PHASE II QUANTITY	PHASE III QUANTITY	TOTAL QUANTITY	UNIT PRICE	AMOUNT
999-07-1*	EA	PRELIMINARY SCREENING		750	750	75.00	56,250.00
999-07-2*	EA	PRE-BURN ANALYSIS		18	18	500.00	9,000.00
999-07-3*	LS	DOCUMENTATION		1	1	15,000.00	15,000.00
999-07-4*	TN	DECONTAMINATION OF SOILS		10000	10,000	40.00	400,000.00
999-07-5*	DY	WATER TREATMENT		80	80	1,600.00	128,000.00
999-07-6*	EA	WATER QUALITY MONITORING TEST - EPA (PER NPDES)		12	12	600.00	7,200.00
		TOTAL ENVIRONMENTAL REMEDIATION	615,450.00				

* Not an FDOT Pay Item No.

TRENCH SAFETY ACT (if applicable for this project)
SECTIONS 553.60-553.64, FLORIDA STATUTES


NOTICE TO BIDDERS:

In order to comply with the Trench Safety Act, the Bidder is required to specify the costs of compliance. These costs **are not a separate pay item.** The Bidder must also reference the Trench Safety Standards which will be in effect during construction, and assure in writing that the Bidder will comply with the applicable Trench Safety Standards.

<u>TRENCH SAFETY MEASURE</u>	<u>UNITS OF MEASURE</u>	<u>QUANTITY</u>	<u>UNIT COST</u>	<u>EXTENDED COST</u>
Trench Shield	LF	5,000	\$1.00	\$5,000.00

TOTAL \$ 5,000.00

Jean-Noel Yelly
Printed Name


Signature
Senior Vice President -
Construction Operations

HUBBARD CONSTRUCTION COMPANY
Bidder Name

March 22, 2006
Date

BIDDER INFORMATION

Bidder shall complete the following information and include with their bid submittal.

Bidder Information

CONTRACTING OFFICER	TITLE	OFFICER'S FULL LEGAL NAME
	President	Luc Bodson
*	Vice-President Construction Operations	Jean-Noel Velly
	Secretary	P. Frederick O'Dea, Jr.
	Treasurer	P. Frederick O'Dea, Jr.
	Resident Superintendent	Ernest J. Wolf

Indicate with an asterisk (*) in the first column, which officer will sign the resulting contract. If other than the President, include a copy of the corporate resolution which gives express authority for execution of the specific proposal and contract documents. Each Bidder must assure that the officer information provided is in accordance with the Bidder's corporate registration supplied to the Secretary of State.

EXPERIENCE OF BIDDER

NAME OF BIDDER HUBBARD CONSTRUCTION COMPANY

The Bidder shall provide the following information regarding experience within the past three years in this particular scope of work.

Bidder must demonstrate ability to construct projects of similar complexity, nature and size as this project. Under Client's Name and address, please include Contact's name, Telephone Number and Fax Number. Exhibit "B"

DATE OF CONTRACT	CLIENT'S NAME & ADDRESS:		CONTRACT AMOUNT
	PH	FX	\$
Project & Location:			

DATE OF CONTRACT	CLIENT'S NAME & ADDRESS:		CONTRACT AMOUNT
	PH	FX	\$
Project & Location:			

DATE OF CONTRACT	CLIENT'S NAME & ADDRESS:		CONTRACT AMOUNT
	PH	FX	\$
Project & Location:			

DATE OF CONTRACT	CLIENT'S NAME & ADDRESS:		CONTRACT AMOUNT
	PH	FX	\$
Project & Location:			

Do you have any similar work in progress at this time? X Yes ___ No

Length of time in business: 86 Years (Minimum three (3) years required)

Bank or Financial references: (Include Contact Name and telephone number)

Wachovia Bank, N.A., Brian Hamilton, Vice President 407-649-5235

**Request for Taxpayer
Identification Number and Certification**

Give form to the
requester. Do not
send to the IRS.

Print or type
See Specific Instructions on page 2.

Name HUBBARD CONSTRUCTION COMPANY	
Business name, if different from above	
Check appropriate box: <input type="checkbox"/> Individual/ Sole proprietor <input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Partnership <input type="checkbox"/> Other ▶	<input type="checkbox"/> Exempt from backup withholding
Address (number, street, and apt. or suite no.) 1936 Lee Road	Requester's name and address (optional)
City, state, and ZIP code Winter Park, FL 32789	
List account number(s) here (optional)	

Part I Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. For individuals, this is your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the Part I instructions on page 3. For other entities, it is your employer identification number (EIN). If you do not have a number, see **How to get a TIN** on page 3.

Social security number								

or

Employer identification number								
5	9	0	5	9	4	2	9	8

Note: If the account is in more than one name, see the chart on page 4 for guidelines on whose number to enter.

Part II Certification

Under penalties of perjury, I certify that:

1. The number shown on this form is my correct taxpayer identification number (or I am waiting for a number to be issued to me), and
2. I am not subject to backup withholding because: (a) I am exempt from backup withholding, or (b) I have not been notified by the Internal Revenue Service (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or (c) the IRS has notified me that I am no longer subject to backup withholding, and
3. I am a U.S. person (including a U.S. resident alien).

Certification instructions. You must cross out item 2 above if you have been notified by the IRS that you are currently subject to backup withholding because you have failed to report all interest and dividends on your tax return. For real estate transactions, item 2 does not apply. For mortgage interest paid, acquisition or abandonment of secured property, cancellation of debt, contributions to an individual retirement arrangement (IRA), and generally, payments other than interest and dividends, you are not required to sign the Certification, but you must provide your correct TIN. (See the instructions on page 4.)

Sign Here	Signature of U.S. person ▶ <i>Jean-Noel Velly</i>	Date ▶ March 22, 2006
-----------	--	------------------------------

Purpose of Form

A person who is required to file an information return with the IRS, must obtain your correct taxpayer identification number (TIN) to report, for example, income paid to you, real estate transactions, mortgage interest you paid, acquisition or abandonment of secured property, cancellation of debt, or contributions you made to an IRA.

U.S. person. Use Form W-9 only if you are a U.S. person (including a resident alien), to provide your correct TIN to the person requesting it (the requester) and, when applicable, to:

1. Certify that the TIN you are giving is correct (or you are waiting for a number to be issued),
2. Certify that you are not subject to backup withholding, or
3. Claim exemption from backup withholding if you are a U.S. exempt payee.

Note: If a requester gives you a form other than Form W-9 to request your TIN, you must use the requester's form if it is substantially similar to this Form W-9.

Foreign person. If you are a foreign person, use the appropriate Form W-8 (see **Pub. 515**, Withholding of Tax on Nonresident Aliens and Foreign Entities).

Nonresident alien who becomes a resident alien.

Generally, only a nonresident alien individual may use the terms of a tax treaty to reduce or eliminate U.S. tax on certain types of income. However, most tax treaties contain a provision known as a "saving clause." Exceptions specified in the saving clause may permit an exemption from tax to continue for certain types of income even after the recipient has otherwise become a U.S. resident alien for tax purposes.

If you are a U.S. resident alien who is relying on an exception contained in the saving clause of a tax treaty to claim an exemption from U.S. tax on certain types of income, you must attach a statement that specifies the following five items:

1. The treaty country. Generally, this must be the same treaty under which you claimed exemption from tax as a nonresident alien.
2. The treaty article addressing the income.
3. The article number (or location) in the tax treaty that contains the saving clause and its exceptions.
4. The type and amount of income that qualifies for the exemption from tax.
5. Sufficient facts to justify the exemption from tax under the terms of the treaty article.

State of Florida)
)ss
County of Orange)


Senior Vice President -

(5) The prices quoted in the attached Bid are fair and proper and are not tainted by any collusion, conspiracy, connivance or unlawful agreement on the part of the Bidder or any of its agents, representatives, owners, employees or parties in interest, including this affiant.

Title: Senior Vice President -
Construction Operations

STATE OF Florida)
) ss
COUNTY OF Orange)

The foregoing instrument was acknowledged before me this 22nd day of
March, 2006, by Jean-Noel Velly who is personally
known to me or who has produced N/A identification.



Wendy J. Vickery
Print Name Wendy J. Vickery
Notary Public in and for the County and State
Aforementioned

My commission expires: June 19, 2007

**ATTACH AND INCLUDE THIS PAGE OF NONCOLLUSION AFFIDAVIT OF BIDDER AS
PART OF BID FORM; FAILURE TO DO SO SHALL BE CAUSE FOR DISQUALIFICATION
OF YOUR BID.**

CERTIFICATION OF NONSEGREGATED FACILITIES

The Bidder certifies that he does not maintain or provide for his employees any segregated facilities at any of his establishments, and that he does not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. The Bidder certifies further that he will not maintain or provide for his employees any segregated facilities at any location under his control where segregated facilities are maintained. The Bidder agrees that a breach of this certification will be a violation of the Equal Opportunity clause in any contract resulting from acceptance of this Bid. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms and other storage and dressing areas, parking lots, drinking fountains, recreation or entertainment area, transportation and housing facilities provided for employees which are segregated by explicit directive, or are in fact segregated on the basis of race, color, religious disability or national origin, because of habit, local custom, or otherwise. The Bidder agrees that (except where he has obtained identical certifications from proposed subcontractors for specific time periods) he will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity clause, and that he will retain such certifications in his files.

The nondiscriminatory guidelines as promulgated in Section 202, Executive Order 11246, and as amended by Executive Order 11375 and as amended, relative to Equal Opportunity for all persons and implementations of rules and regulations prescribed by the United States Secretary of Labor are incorporated herein.

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C. 1001.

Date: March 22, 2006

By: _____

Print Name: Jean Noel Velly
Senior Vice President -
Title: Construction Operations

Official Address:

1936 Lee Road

Winter Park, FL 32789

(Include Zip Code)

ATTACH AND INCLUDE THIS PAGE AS PART OF BID FORM; FAILURE TO DO MAY BE CAUSE FOR DISQUALIFICATION OF YOUR BID.

NOTICE OF NO BID

IF YOU DO NOT INTEND TO BID ON THIS REQUIREMENT, PLEASE COMPLETE AND RETURN THIS FORM PRIOR TO DATE SHOWN FOR RECEIPT OF BIDS TO: SEMINOLE COUNTY, PURCHASING DIVISION, 1101 EAST FIRST STREET, ROOM #3208, SANFORD, FLORIDA 32771.

WE, THE UNDERSIGNED, HAVE DECLINED TO BID ON YOUR BID, CC-0569-06/TLR FOR THE FOLLOWING REASON(S):

- ____ Specifications are too "restrictive", i.e., geared toward one brand or manufacturer only (please explain reason below).
- ____ Insufficient time to respond to invitation to bid.
- ____ We do not offer this type of service.
- ____ Our schedule would not permit us to perform.
- ____ Unable to meet specifications.
- ____ Unable to meet bond requirements.
- ____ Specifications unclear (please explain below).
- ____ Other (please specify below).

Remarks: _____

WE UNDERSTAND THAT IF THE "NO BID" LETTER IS NOT EXECUTED AND RETURNED, OUR NAME MAY BE DELETED FROM THE LIST OF QUALIFIED BIDDERS FOR SEMINOLE COUNTY BOARD OF COUNTY COMMISSIONERS FOR FUTURE PROJECTS.

Signature and Title

Typed Name and Title

Company Name

Address

Telephone Number

Date

Fax Number

**AMERICANS WITH DISABILITIES ACT
AFFIDAVIT**

The undersigned CONTRACTOR swears that the information herein contained is true and correct and that none of the information supplied was for the purpose of defrauding COUNTY.


The CONTRACTOR will not discriminate against any employee or applicant for employment because of physical or mental handicap in regard to any position for which the employee or applicant for employment is qualified. The CONTRACTOR agrees to comply with the rules, regulations and relevant orders issued pursuant to the Americans with Disabilities Act (ADA), 42 USC s. 12101 *et seq.* It is understood that in no event shall the COUNTY be held liable for the actions or omissions of the CONTRACTOR or any other party or parties to the Agreement for failure to comply with the ADA. The CONTRACTOR agrees to hold harmless and indemnify the COUNTY, its agents, officers or employees from any and all claims, demands, debts, liabilities or causes of action of every kind or character, whether in law or equity, resulting from the CONTRACTOR's acts or omissions in connection with the ADA.

CONTRACTOR: HUBBARD CONSTRUCTION COMPANY
Signature: _____
Printed Name: Jean-Noel Velly
Title: Senior Vice President - Construction Operations
Date: March 22, 2006

Affix Corporate Seal

STATE OF Florida)
) ss
COUNTY OF Orange)

The foregoing instrument was acknowledged before me this 22nd day of March, 2006, by Jean-Noel Velly of HUBBARD CONSTRUCTION COMPANY firm), on behalf of the firm. He/She is personally known to me or has produced N/A identification.



Wendy J. Vickery
Print Name Wendy J. Vickery
Notary Public in and for the County
and State Aforementioned

My commission expires: June 19, 2007



Exhibit "A"

AC#1761169

STATE OF FLORIDA

DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION
CONSTRUCTION INDUSTRY LICENSING BOARD

SEQ# L04112400219

DATE	BATCH NUMBER	LICENSE NBR
11/24/2004	040174794	CGC1508130

The GENERAL CONTRACTOR
Named below IS CERTIFIED
Under the provisions of Chapter 489 FS.
Expiration date: AUG 31, 2006

WOLF, ERNEST JOSEPH
HUBBARD CONSTRUCTION COMPANY
P.O. BOX 547217
ORLANDO FL 32854

JEB BUSH
GOVERNOR

DISPLAY AS REQUIRED BY LAW

DIANE CARR
SECRETARY

**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

Exhibit "B"

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10313	John Young Parkway Design Build Orange County, Florida Y1-819-DB	Orange County, Florida 201 S. Rosalind Ave - 3rd Floor Orlando, FL 32801 407-836-7917 Mr. Chuck Dixon	This project consists of widening/surfacing of John Young Parkway from a four lane divided roadway to a six lane divided roadway including a bicycle lane in each direction. Also included is the installation of 8,900 lf of 24" force main. The project extends from the north approach slab of the John Young Parkway Bridge of the Florida Turnpike, north to the I-4 Interchange, approximately 3.7 miles	\$9,488,971	October 30, 2002 February 2006	99%
10314	I-4/US 27 Interchange Design Build CR 557 to Osceola County Polk County, Florida FDOT No. 201204-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consists of widening I-4 36 ft eastbound and westbound for 7 miles, a new interchange at US 27, reconstructing I-4 eastbound and westbound for 1 mile and a new bridge at CR54.	\$66,296,029	November 4, 2002 February 2006	99%
10317	SR 436 Widening SB Ramp SR 526 to SR 552 Orange County, Florida FDOT No. 239454-2-52-01 (T5105)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consists of inside and outside widening of SR436 from the southbound ramp of SR528 to SR552, construction of drainage and utilities, milling of existing roadway and asphalt paving.	\$29,890,417	April 15, 2003 February 2006	94%
10320	Western Beltway Project No. 654 Part C McKinney Rd to N of CR 535 Orange County, Florida	Orlando-Orange County Expressway Authority 525 South Magnolia Avenue Orlando, Florida 32801-4414 407-316-3800 Mr. Ben deralling, Dir. Of Constr.	This is a new section of the Western Beltway running from McKinney Rd. to north of CR535. The length of the roadway is 4.9 miles, includes 12 bridges at 7 locations.	\$34,728,242	December 1, 2003 February 2006	99%
10321	US 441 Osceola County, Florida from Osceola Pkwy to Taft Vineland Road FDOT No. 239725-1-52-01 (T5040)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Clearing, earthwork, drainage, paving, utility, signals, signs, and pavement markings	\$33,259,029	March 15, 2004 September 2, 2006	72%

**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10322	SR 408 Widening from Hiawassee Rd to Tampa Avenue OOCEA # 252B	Orlando-Orange County Expressway Authority 525 South Magnolia Avenue Orlando, Florida 32801-4414 407-316-3800 Mr. Ben Dreiling, Dir. Of Constr.	The project consists of widening approximately 4.5 miles of inside and outside widening from Hiawassee Rd to Tampa Avenue; six bridge widening, demo of existing mainline plaza and four ramp plazas; 7 bridge beautifications; planter walls; sound walls; drainage; roadway lighting; fiber optic network; signing and pavement markings.	\$73,952,972	June 1, 2004 December 6, 2006	44%
10323	OUC SR 500 (US 441) Utility Adjustments	Orlando Utility Commission 500 S Orange Avenue Orlando, FL 32802	Work consisted of water line relocations and adjustments to resolve conflicts with the storm drainage and other improvements.	\$1,017,698	May 28, 2004 February 2006	80%
10325	Tuskawilla Middle School Seminole County	Suitt Construction 495 North Keller Road, STE 101 Maitland, FL 32751 407-834-2300 Mr. Tony Salvo, Sr. Estimator	This project involved demolition, earthwork, grading, asphalt pavement, storm drainage, sanitary sewer, fire lines, potable water and electrical sleeves for the new school.	\$1,582,290	July 6, 2004 July 31, 2006	51%
10327	SR 15 (SR 436 & Hoffner) Orange County FDOT No. 409093-1-52-01 (T5061)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project included adding turn lane to existing road. Widening on both sides, mill and resurface existing, and storm drainage improvements.	\$889,906	September 1, 2004 February 2006	91%
10329	Gatorland Parking Lot Expansion	Godwin's Gatorland, Inc. 14501 South Orange Blossom Trail Orlando, FL 32837 407-855-5496 Mr. Mark McHugh	Demolition of existing parking lot and construction of new parking lot with storm drainage. Also included median modifications to SR 441.	\$463,801	October 4, 2004 February 2006	79%
10331	Target Orlando East	MCP Retail, Inc. TARG231 West Park Avenue Winter Park, FL 32789 407-599-4444	Work consists of clearing, earthwork, grading, pavement and base, storm drainage, sanitary sewer, water and firemain, and flatwork.	\$2,188,739	October 4, 2004 February 2006	99%

**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10332	Florida Hospital South Bed Tower: Rollins Street Realignment Orlando, Florida	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Work consists of clearing trees and landscaping, traffic maintenance, demolition of pavement, curbs, sidewalks and certain utilities, storm drainage, sanitary sewer, water lines, paving and curbs and pavement markings.	\$1,856,717	November 23, 2004 March 2006	77%
10333	Floridays Orlando Resort Drive/ Vineland Avenue Orlando, Florida	Floridays Development Corp 3700 South Tamiami Trail STE 201 Sarasota, FL 32216 941-362-9377 Mr. Mark Harvey	This project is a 20 acre site in which we will be doing clearing, earthwork and grading, pavement and curbing, storm drainage, sanitary sewer, retaining wall and sodding.	\$3,926,792	December 3, 2004 May 12, 2006	77%
10335	SR 417 Seminole Cty Expressway Seminole County FDOT No. 413669--52-01 (T4032)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project includes widening on SR 417 with storm pipe and selective tree removal.	\$615,085	December 8, 2004 March 2006	68%
10336	SR 526 Orange Cty FDOT No. 411727-1-52-01 (T5076)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consists of demolition and installation of new curb ramps and adjust manholes for mill and resurface. Some sod replacement & MOT.	\$473,088	March 24, 2005 March 2006	85%
10337	Florida Hospital Alden Garage	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of demolishing existing pavement and improvements, excavate for foundation and install drainage improvements.	\$126,866	November 8, 2004 January 2006	95%

**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10338	Florida Hospital Temporary Entrance	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of constructing a temporary entrance to Florida Hospital's main entry. Work included demolition, excavation and pavement.	\$424,248	January 14, 2005 January 2006	80%
10339	OIA BP-352 Rehab Taxiways E&F	Greater Orlando Aviation Authority 5850 Cargo Road Orlando, FL 32827 407-825-4684 Mr. Stan Thornton, Dir. Of Engineering & Constr.	Project includes clearing, earthwork, drainage, paving, electrical, signs and pavement markings for widening and reconstruction of Taxiways E & F.	\$14,484,997	March 1, 2005 November 8, 2006	34%
10340	Old Winter Garden Road	Orange County Florida 400 E. South Street - 2nd Floor Orlando, Florida 32801 407-836-5468	Project consists of roadway reconstruction, bridge widening, drainage and utilities.	\$12,443,720	May 31, 2005 May 31, 2007	31%
10341	Florida Hospital Altamonte	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of parking lot and utility modifications. Work includes demolition, grading, storm drainage, utilities and pavement.	\$1,726,644	April 18, 2005 December 31, 2006	40%
10342	Posner Park Access - 1A	Boardwalk and Baseball, Inc. C/O Kilson and Partners PO Box 992 Florham Park, NJ 07932 236-9600 Broderick	Project includes a turn lane installation.	\$1,176,113	September 2005 March 2006	60%



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK IN PROGRESS

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10344	Posner City Center - 1B	Boardwalk and Baseball, Inc. C/O Kitson and Partners PO Box 992 Florham Park, NJ 07932 973-236-9600 John Broderick	Project consists of infrastructure road and utilities.	\$1,938,798		5%
10345	Polk County Landfill	Polk County Purchasing Division 2470 Clower Lane, Drawer AS06 PO Box 9005 Bartow, FL 33830 863-534-5610 Mr. Dennis Davis	Work consists of access roads, storm drainage, lift stations, leachate force mains, enlarging above grade glass lined steel tanks, earthwork and sand drainage blanket, including cell liner for a 59 acre landfill expansion at the North Central Landfill near Bartow, FL.	\$23,176,600	November 1, 2005 October 31, 2006	6%
10346	Florida Hospital South - Tower	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Consists for site work for patient tower expansion.	\$2,736,922	November 1, 2005 September 19, 2009	1%
10347	Hughes Supply Mega Center	Hughes Supply, Inc 576 NE 23rd Ave. Gainesville, FL 32609 352.264.3030 Roger Stephens	Site work for new warehouse.	\$3,883,230	November 21, 2005 June 21, 2006	11%

**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
10349	Osceola Corporate Center Mary Louis Lane Roadway Development	Deerfield Land Corporation 14901 South Orange Blossom Trail Orlando, FL 32837 407-847-1846 Mr. Thomas M Roll	Construct new roadway with drainage. Reconstruct 1,800lf of Orange Avenue	\$1,718,518	January 2, 2006 May 31, 2006	1%
10350	Villages @ Imagine	Hardin-Led core Construction 4700 Millennia Blvd, STE 350 Orlando, FL 32839 407-353-2233 Mr. Don May	earthwork, utilities, drainage, paving and curbs.	\$4,376,000	January 3, 2006 November 2007	1%
20088	Water Utilities	Jacksonville Electric Authority 6674 Commonwealth Avenue Jacksonville, FL 32254 904-665-8473 Ms. Jackie B Scheel, Proj. Mgr.	Commercial water meter replacement, water main extensions.	\$1,731,781	November 23, 2002 February 2006	95%
20090	SR 9A (I-295) from the St Johns Cty Line North to SR 90 (I-295) Duval County, Florida FDOT No. 213351-5-52-01 (T2103)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Widening and reconstruction of exit ramp(s), regrade ditches, drainage, construct wet detention pond, Bridge, Box Culvert, Exits, & Utility. 2.34 miles.	\$10,802,514	June 15, 2003 January 2006	93%
20097	SR 115 Southside Blvd Duval County FDOT # 209664 (T2093)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project includes clear & grub, pavement removal, excavation concrete, grading, storm drain, flatwork, grassing and erosion control.	\$665,028	December 20, 2004 January 2006	71%



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK IN PROGRESS

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
20098	SR 212 Beach Blvd Duval County FDOT # 209513 (T2067)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consists of 6 lane reconstruction of the existing 4 lane rural roadway. This includes drainage, 2 detention ponds, 2 box culverts and water and sewer.	\$23,934,139	March 1, 2005 November 25, 2007	27%
20099	North Shetland Drive from CR 244 NW to Aberdeen	England-Thims & Miller 14775 St Augustine Road Jacksonville, FL 32258 904-642-8990 Scott Wild	Project includes new construction of 2 lane urban roadway to include storm drain, pond, water, sewer and re-use water.	\$2,246,500	October 21, 2005 October 15, 2006	16%
20100	CR 244 Northwest from CR 244 South to CR 223 South	England-Thims & Miller 14775 St Augustine Road Jacksonville, FL 32258 904-642-8990 Scott Wild	Project consists of new construction of 2 & 3 lane urban roadway including storm drain, 7 ponds, 5 box culverts, water sewer and re-use water.	\$13,990,000	October 21, 2005 October 15, 2006	6%
20101	CR 215, Clay County FDOT # 413612 (T2134)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Extend 3 each box culverts, pave shoulders, regrade shoulders, rework shoulders and retrofit guardrail traffic rail barrier.	\$900,000	December 1, 2005 February 28, 2006	1%
20102	Chaffee Pointe	Kennard Construction, Inc, 3225 Southside Blvd, Blvd #2 Jacksonville, FL 32216 904-642-9003 Mr. Thomas Kennard	Sitework prep and parking pavement that includes storm drainage and utilities.	\$277,500	October 17, 2005 January 2006	40%
20103	SR 9A, Duval County FDOT # 213251 (T2136)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Clear & grub, removal of existing concrete pavement, reg excavate embankment, box culverts, storm drain extensions and concrete ditch work.	\$1,940,610	January 16, 2006 December 31, 2006	1%



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK IN PROGRESS

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
30028	US 19 Coachman Rd & Sunset Rd Pinellas County, Florida FDOT No. 256888-1-52-01 (T2063)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consists of clearing & grubbing, earthwork, re-wall, sheet pile bridge work, base, storm drainage, sodding, signage electrical signals, waste lines & gas lines.	\$47,124,846	April 28, 2003 December 26, 2006	51%
30029	FDOT US 41 Sarasota Sarasota County FDOT # 198018 (T1125)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project includes clearing, earthwork, drainage, asphalt paving, utility, bridge construction, signals, signs and pavement markings.	\$32,362,115	July 12, 2007	2%
30030	I-275 Hillsborough County Soundwall, Hillsborough County FDOT # 258443 (T5041)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Consists of clearing, earthwork, drainage, asphalt paving, bridge construction, signals, signs, pavement markings and soundwall construction.	\$13,571,161	December 1, 2005 November 5, 2006	1%
30031	I-75, Hillsborough/Pasco County FDOT # 258413 (T7113)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project entailed roadway, signing, lighting, pavement markings, widening of an existing bridge over Cypress Creek and box culvert extensions.	\$8,187,912	January 1, 2006 December 6, 2007	1%
70010	Northlake (Reliever) Military Trail to Garden Rd Palm Beach County, FL Project No. 91507A	Board of County Commissioners Palm Beach County 160 Australian Ave, STE 503 Palm Beach, FL 33406 561-684-4180 Mr. Jack Provence	The project consists of all necessary work to construction Northlake (Reliever), as a two-lane roadway with bridge construction over I-95 and includes improvements to Investment Lane from a two-lane roadway to a two-lane roadway with service roads and a roundabout.	\$7,044,381	May 1, 2002 February 2006	90%



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK IN PROGRESS

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
70013	I-95 (South of Gateway to South of 6th Avenue) Palm Beach County, FL FDOT No. 231937-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project consists of all work necessary to construct I-95 HOV lanes from South of Gateway Blvd to south of 6 th Avenue South in Palm Beach Co. Replace pedestrian overpass and widening of the 12 th Ave South bridges.	\$33,505,977	September 20, 2003 May 29, 2006	82%
70014	I-95 HOV 10th Avenue to Summit Palm Beach County, FL FDOT No. 231918-2-52-01 (T4016)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project added lanes and reconstructed SR 9 (I-95) from 10 th Avenue to a point N of Summit Blvd. It also had bridge work, demolition, a MSE wall, temporary wire wall, temporary steel sheeting, import fill, limerock base, asphalt overbuild, temporary pavement, permanent asphalt, storm drainage, roadway lighting, soundwall, and grassing and sodding.	\$45,488,820	January 5, 2004 October 6, 2007	42%
70016	SR 708 Blue Heron from W of Military Trail to W of I-95 Palm Beach County, FL FDOT No. 229648-1-52-01 (T4018)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consisted of all work necessary for the widening and reconstruction of SR 708 from a four lane divided to a six lane divided roadway. Also included drainage improvements, expansion of the VA Hospital Lake number 6 pond, signalization, lighting, signing and pavement markings and a privacy wall.	\$6,600,774	February 2, 2004 February 2006	90%
70017	Super Target T-1935 SR 7 & Okeechobee Blvd Palm Beach County, FL	Target Corporation 1000 Nicolette Mall Minneapolis, MN 55403 904-347-3662 Mr. Joe Rozier, Owners Rep.	Project consists of sitework, earthwork grading, utilities, asphalt & concrete paving, concrete curbs & sidewalks, markings and offsite modifications on 21 acre site.	\$3,382,792	February 19, 2004 January 2006	96%



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK IN PROGRESS**

12-30-2005

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	PERCENT COMPLETE
70018	Contractor's Business Park Okeechobee Blvd & Vista Pkwy Palm Beach County, FL	CD74 Contractors Business Park Vista Center 1350 E Newport Center Dr STE 202 Deerfield Beach, FL 33442 954-428-4585 Mr. Greg Govan	Project consists of sitework on a 18 acre site for 11 office buildings with borrow, asphalt, utilities and miscellaneous work.	\$2,798,490	March 19, 2004 January 2006	96%
70019	I-95 Southern to PB Lake Blvd Palm Beach County FDOT No. 231919-3-52-01 (T4032)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project includes construction of HOV lane and replacement bridges.	\$75,872,242	August 1, 2004 June 11, 2009	16%
70020	Cobblestone Village @ RPB Okeechobee Blvd & SR 7	Cobblestone Village @ RPB 2030 Hamilton Place Blvd. STE 500 Chattanooga, TN 37421 423-855-0000	Project included sitework on a 5 acre development for retail stores adjacent to Super Target	\$907,317	July 19, 2004 January 2006	89%
70023	CR 707 Indian River Drive St. Lucie County FDOT No. 417432-1-78-02	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project includes reconstruction of embankment - slope protection along CR 707. Emergency repair project.	\$11,705,792	October 26, 2004 January 2006	97%
70024	Target T-1941	Williams Company SE 2301 Silver Star Road Orlando, FL 32804 407-295-2530 Mr. Mike Ricotta	Project consists of development of a 20 acre site for a standard Target store	\$4,020,845	January 27, 2005 March 2006	84%



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK COMPLETED IN 2005**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10307	Orange County Landfill Cell 9 Orange County, Florida IFB No. Y2-750-PH	Board of City Commissioners Orange County, Florida 400 E South St., 2nd Floor Orlando, FL 32802-1393 407-836-7917 Mr. Chuck Dixon	This project will provide the county with a new 65-acre lined Class I solid waste disposal area and associated support & ancillary facilities.	\$27,355,965	September 16, 2002 June 9, 2005
10311	SR 44 Volusia County, Florida FDOT No. 240805-3-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project involves the realignment and reconstruction of approximately 4 miles of SR 44 in Volusia County, from a 2-lane rural to a 4-lane divided roadway. Limits extend from approximately ¼ mile west of CR 4118 (Pioneer Trail) to ¼ mile west of SR 415 (near Samsula). Reconstruction includes ½ mile of Pioneer Trail and its intersection at SR 44.	\$11,128,948	November 4, 2002 June 22, 2005
10319	OUC 436 Waterline Waterline Conflict Resolution Curry Ford Road to Lee Vista Orange County, Florida	Orlando Utilities Commission 500 S Orange Avenue Orlando, Florida 32802 407-649-4418 Mr. Brad Jewell	This project consisted of water line relocations and adjustments to resolve conflicts with the storm drainage and other improvements on the FDOT 436 project.	\$1,008,185	June 2, 2003 December 3, 2005
10324	SR 46 (OPC) FDOT # 240229 Seminole County, Florida	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Road rehabilitation due to Hurricanes.	\$538,458	June 17, 2004 March 1, 2005
10326	Trinity Preparatory Track Expansion	Trinity Preparatory School 5700 Trinity Prep Lane Winter Park, FL 32792 407-671-4140	Project included Track expansion and improvements.	\$319,508	August 2, 2004 January 5, 2005



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK COMPLETED IN 2005**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10328	Kissimmee Gateway Airport Blastpad	City of Kissimmee 301 N Dyer Road, Ste 101 Kissimmee, FL 34741 (407) 847-4600 Mr. Terry Lloyd	Project consists of grading and basework.	\$57,182	August 4, 2004 February 15, 2005
10330	Emergency Repair of 17/92 at Lake Monroe Seminole County FDOT No. 4175672-72-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The scope of the work includes restoring the shoulder and roadway in two phases. Phase I: Place embankment material along US 17-92 to approximately 10 feet from edge of pavement with the goal of opening the roadway to traffic. Phase II: Once the roadway is safe to allow traffic, continue placing embankment material to it's pre-storm locations	\$734,232	September 27, 2004 February 20, 2005
20092	SR 115 (Lem Turner Rd) from I-295 to Nassau Cty Line Duval County, Florida FDOT No. 209713-2-52-01 (T2022)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project includes clearing & grubbing, grading, widening, storm drain, erosion control and grassing.	\$985,644	September 8, 2003 October 5, 2005
20094	SR 9A (I-295) Commonwealth Ave to S of Trout River Bridge Duval County, Florida FDOT No. 213259-2-52-01 (T2054)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The improvement under this contract consists of clear & grub, dewatering, storm drain, slab subgrade, riprap, shoulder rework and grassing.	\$997,160	April 5, 2004 January 15, 2005
20095	8th Street Roadway Improvements from Boulevard St to Liberty St Duval County, Florida Jax Proj. No. BCP-1018-04	City of Jacksonville 117 W Duval Street, STE 330 Jacksonville, FL 32202 904-630-1646 Mr. Dave Schneider	Reconstruction of 3 lane 8 th Street roadway from Boulevard St to Main St. (.042 miles) in 5 phases.	\$4,527,017	February 24, 2004 December 2005



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2005

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
20096	SR 15 (US 1) from SR 111 to Wagner St Duval County, Florida FDOT No. 209642-2-52-01 (T2030)	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consists of clearing & grubbing, grading, storm drain, box culvert ext., RAP turnouts, flatwork, shoulder rework and grassing.	\$1,544,588	August 14, 2004 June 15, 2005
30026	I-4 US 98 Interchange Polk County, Florida FDOT No. 201213-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The improvements under this contract consist of new roadway construction, milling, drainage improvements widening, resurfacing, signalization, lighting and the removal and replacement of the existing overpasses at the interchange of I-4 and US 98 for a total length of 2,375 meters in Lakeland, Polk Co.	\$30,491,537	April 1, 2002 September 30, 2005
30027	Lee Roy Selmon Expwy SR 618 from 78th St to I-75 Hillsborough County, FL	Tampa-Hillsborough County Expressway Authority 412 E Madison St, STE 800 Tampa, Florida 33602 813-272-3730 Ms. Nancy Marino	The project will enable motorists on the Lee Roy Selmon Crosstown Expressway to enter and exit the Tampa-Hillsborough Co. Expressway Authority's Reversible Lanes between downtown Tampa and Brandon, Florida. The project is located between 78 th Street and I-75, a distance of approximately 2.67 miles.	\$31,035,523	October 15, 2002 October 5, 2005



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2004

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10287	BP-S002 Mid Crossfield Taxiway Orlando, Florida	Greater Orlando Aviation Auth. 5850 Cargo Road Orlando, Florida 32728-4399 407-825-2461 Mr. Stan Thornton, Dir. Of Engineering & Constr.	The work consists of extensions of the Taxiway E and F bridges to the east, construction of the new Secure Road Bridge, construction and partial realignment of the South Access road to two lanes in each direction and the construction of the new Secure Rd A.	\$40,038,896	*January 25, 2001 June 9, 2004
10298	I-4 Auxiliary Lanes Design Build Orange County, Florida FDOT No. 242499-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This Design Build project consists of 13.6 miles of widening or resurfacing of I-4 with new auxiliary lanes/shoulders. 12 bridge locations on I-4 will be widened to the inside or outside.	\$58,831,179	*January 25, 2001 May 9, 2004
10302	I-4/Turnpike Interchange to Kirkman Road Orange County, Florida FDOT No. 242496-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consists of the 1.1 miles of roadway widening, milling and resurfacing of I-4 from E of the Turnpike to Kirkman Rd. Re- construction on the Turnpike at I-4. Turnpike construction includes the replacement of the bridges over I-4.	\$13,979,760	October 1, 2001 January 27, 2004
10305	SR 438 Silver Star Road Orange County, Florida FDOT No. 239238-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project is a 3-mile reconstruction of SR 438 (Silver Star Road) to a 4 to 6 lane urban section. This involves construction roadway surface, curb and gutter, sidewalk, underground storm sewer systems, storm water management facilities, and underground utility systems. The project extends from west of Clark Road to just east of Hiawasse Road.	\$13,135,060	January 3, 2002 May 18, 2004



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2004

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
20089	SR 228 College Street Baker County, Florida FDOT No. 207915-2-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Clearing, demolition of concrete pavement, grading, widening, storm drain, flowfill, and retaining wall.	\$605,294	April 1, 2003 March 2004
20091	SR 15 (US 17) McIntosh Ave - Duval County Line Clay County, Florida FDOT No. 208228-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The improvements under this contract consist of new roadway construction, milling, drainage improvements, widening, resurfacing, signalization, lighting and the removal and replacement of Bridge Numbers 160310 and 160311 on State Road 400 (I-4).	\$6,322,605	May 8, 2003 October 22, 2004
20093	SR 111 (Edgewood Ave) from SR 10 to Susquehanna Duval County, Florida FDOT No. 209512-2-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project includes clearing & grubbing, grading, dewatering, storm drain, temporary sheet pile, Rip Rap and grassing.	\$68,600	November 2, 2003 April 26, 2004
70008	I-95 South of Linton to Atlantic Palm Beach Cty, Florida FDOT No. 231916-1-52-01	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consisted of clearing & grubbing, earthwork, stabilization, base, asphalt, storm drainage, piling, bridge work, temp & perm muse walls, sheet piling, roadway lighting, signalization, signs, landscaping & grassing.	\$63,378,571	November 1, 2000 January 16, 2004



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK COMPLETED IN 2004**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
70011	Burns Road Military Trail to Riverside Dr City of Palm Bch Gardens, Florida Project No. 00-4107B	City of Palm Beach Gardens 10500 N Military Trail Palm Bch Gardens, FL 33410 772-286-3883 Mr. Ray Prescott	The project consists of all work necessary to reconstruct Burns Road west, to a five-lane roadway with four lane divided roadway on Burns Road from Military Trail to Riverside Drive.	\$3,884,482	June 3, 2002 May 12, 2004
70022	Lake Worth Road Emergency Bridge	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Hurricane aftermath emergency repairs.	\$88,110	September 25, 2004 October 15, 2004



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2003

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10312	SR 435 (Kirkman Rd) Orange County, Florida FDOT No. 239288	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project involves the reconstruction/widening of Kirkman Road, a 4-lane roadway, from a point south of Conroy Road north 4.5 miles to SR 50, including the inside/outside widening of a 4 span bridge over the Florida Turnpike.	\$16,028,635	January 7, 2002 November 27, 2003
10315	SR 438 Resurfacing Orange County, Florida FDOT No. 407158	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consists of various resurfacing on Princeton St., Silver Star Road and John Young Parkway. Also includes some clearing & grubbing, earthwork, base storm drainage and sodding.	\$711,519	March 21, 2003 September 3, 2003
10318	Little Lake Bryan Parcel 4 Osceola County, Florida Bid # 9041C-03LF	The Celebration Company PO Box 10321 Lake Buena Vista, FL 32830 407-566-4055 Fax 407-566-4388	Project included clearing, earthwork, storm drainage, landscape restorations, grassing, erosion control, and concrete sidewalks.	\$641,554	June 30, 2003 Sept. 30, 2003
20084	SR 9 (I-95) North/Airport Duval County Jacksonville, Florida FDOT No. 213271-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The 7.92 miles project included widening inside lanes of SR-9 (I-95) from N I-295 north to Nassau County Line	\$20,927,034	*November 4, 2001 June 23, 2003



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2003

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
30022	I-275 Fletcher to US 41 Tampa, Florida Hillsborough County, FL FDOT No. 258412-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The improvements under this contract consists of widening and reconstruction on I 275 from S. of Fletcher Ave. to N. of US 41. Over pass for a distance of 3705 meters in Tampa, FL.	\$19,400,518	*May 16, 2000 March 24, 2003
70015	BAK Middle School 3701 North Shore Drive West Palm Beach, FL	Centex Rooney Construction Co 7901 SW 6th Court Plantation, FL 33324 561-272-8375 ext 23 John Southard	Clearing & grubbing, earthwork & grading, asphalt pavement, concrete, storm drainage, sanitary sewer, water distribution system, pavement markings and signage	\$541,076	August 14, 2003 November 1, 2003



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2002

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10272	FDOT SR 530 US 192 - Osceola County FDOT No. 239669-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consisted of 1,800 meters of roadway widening, milling of existing pavement and asphalt paving, 3,700 meters of complete road construction, demolition and replacement of one bridge, extensive hardscaping and landscaping complete with the construction of 3 bus shelters.	\$22,020,800	*October 11, 1999 January , 2002
10275*	OIA BP-301 4th Runway Site Grading Orlando, Florida	Greater Orlando Aviation Auth. 5850 Cargo Road Orlando, FL 32728-4399 407-825-2461 Mr. Stan Thornton, Director Engineering & Construction	This project involved clearing, grubbing, mass grading and drainage. Hubbard cleared a 500-acre swampy area, moved 3 million cy of dirt to fill in the lowlands and built a 2,200 ft long four-barrel box culvert to divert a canal that bisected the runway.	\$25,143,558	*July 1, 2000 May 1, 2002
10281	OIA BP-301 4th Runway Heintzelman Boulevard Orlando, Florida	Greater Orlando Aviation Auth. 5850 Cargo Road Orlando, FL 32728-4399 407-825-2461 Mr. Stan Thornton, Director Engineering & Construction	Project consisted of a new divided 4-lane, 4.5 mile roadway. The project widened the existing 2-lane South Access Road over approximately 1.5 miles to 4-lane divided roadway. The project included 5 bridges, with lengths ranging from 92 to 480 ft, extending 3 box culverts, and constructing 4 new box culverts.	\$35,700,944	*March 13, 2000 November 8, 2002



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2002

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10288	Lake Underhill Road Lockheed Martin	LMC Properties, Inc. 100 S Charles St., STE 1400 Baltimore, MD 21202 407-363-0544 Mr. Frank Lindrum Orlando Central Park	The project included demolition of a portion of the existing two lane Lake Underhill Road between Rouse Road and Alafaya Trail, and construction of a four-lane roadway, median and sidewalks. Construction of a private Loop Road on Lockheed Martin property.	\$8,322,730	August 11, 2000 January 2002
10289	Mall at Millenia Orlando, Florida	Forbes-Taubman 3101 PGA Blvd Palm Beach Gardens, FL 33410 561-622-2115 Mr. Tom Carnes	The project, a regional mall on a 90 acre site, consisted of clearing, mass grading, filling of site, filling for the building, construction of a retention pond, erosion control, storm drainage, sanitary sewer, electrical/ communication duct, paving, curbing, pavement markings/signage and grassing. The site located in the city limits of Orlando is in the southwest corner of Conroy Road and Millenia Boulevard new the Conroy Interchange.	\$14,880,278	August 30, 2000 August 8, 2002
10295	SR 91 (Florida Turnpike) From SR 408 to CR 439 Ocoee, Florida FDOT No. 243013-3-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project was a 2-mile Turnpike road widening project.	\$2,156,690	March 19, 2001 April 9, 2002



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2002

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10296	Universal Boulevard Design Build Contract No. Y1-802-DB	Orange County, Florida 201 S Rosalind Ave - 3rd Floor Orlando, FL 32801 407-836-7917 Mr. Chuck Dixon	This project involves a single contract for the construction of the Universal Boulevard Extension and for the design, permitting, and construction of modifications to the interchange at Orangewood Boulevard and the Beeline Expressway (SR 528). The project consists of two parts. The first part is the construction of 2.195 miles of six lanes divided urban roadway for Universal Boulevard. The second part is the design, permitting, and construction of the Orangewood (Universal) interchange.	\$16,846,445	*July 1, 2001 December 31, 2002
10297	Florida Mall Expansion Sand Lake & Hwy 441 Orlando, Florida	Simon Property Group 100 DeBartolo Place Youngstown, Ohio 44513-3287 330-758-7292 Mr. John Hudran, Purchasing Agent	The project involves the modification to the existing Mall parking lot to accommodate the addition of a new Nordstrom anchor store on the east side of the site. The project consists of the demolition of the existing parking lot, storm drainage modifications, sanitary sewer modifications, modifications to the existing retention pond, design and construction of a sheet pile retaining wall, guardrail, fencing, and the construction of the new parking lot.	\$1,690,903	June 19, 2001 June 14, 2002



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK COMPLETED IN 2002**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10303	Sand Lake Road Bridge Widening Sand Lake Road @ Kirkman Road Orange County, Florida FDOT No. 23931-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Project consists of clearing, earthwork, bridge widening, milling and resurfacing, guardrail, barrier wall, striping and signs.	\$3,674,169	October 1, 2001 November 22, 2002
10306	Grant-Robinson 115KV Line Orlando, Florida	Interstate Construction 3909 Security Park Drive Rancha Cordova, CA 95742 916-351-0622 Mr. Markus Hanson	This underground cable project is located in the City of Orlando, near the downtown area. The project consists of one three phase underground 115 kV circuit installed as part of a 115 kV transmission line connecting OUC's Grant Substation to OUC's Robinson Substation. The single 115 kV underground circuit will be installed in a double circuit concrete encased ductbank and manhole system between a new riser structure located near the intersection of Gore Street and Division Avenue and the GIS termination at OUC's Robinson Substation. The underground duct bank will be approximately 6,800 lineal feet in length.	\$2,924,457	January 2, 2002 September 11, 2002



HUBBARD CONSTRUCTION COMPANY **PROJECTS WORK COMPLETED IN 2002**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
20071	I-95 Rigid Pavement Duval County, Florida FDOT No. 72020-3490 Jacksonville, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project involved pavement replacement from Edgewood Ave to Dunn Ave. The project included concrete pavement rehab, lighting and asphalt shoulders.	\$4,552,522	March 23, 2000 May 2002
20074	SR 115 Southside Blvd Duval County, Florida FDOT No. 209557-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This 3.12-mile project included adding lanes and shoulders to existing divided road from SR9 (I-95 ramps) to SR 202 (J.T. Butler Blvd.)	\$8,400,916	July 28, 2000 May 14, 2002
20075	SR 9 (I-95) St Johns County FDOT No. 213274-1-52-01 Jacksonville, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This 5.6 miles project included adding inside travel lanes and shoulders for divided highway, from the St. Johns Co. Line to north to SR 9A(I-295).	\$10,691,757	September 2000 May 2002
20083	SR 10 (US 90) Duval County FDOT No. 209568-1-52-01 Jacksonville, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project included widening outside lane Brandy Branch, clearing & grubbing, demolition of 2 existing bridges & asphalt /concrete road. Construct box culvert on Brandy Branch. Construction flat slab Bridge on McGirt, reconstruct new road.	\$1,643,031	February 2, 2001 January 12, 2002



HUBBARD CONSTRUCTION COMPANY PROJECTS WORK COMPLETED IN 2002

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
20085	JEA Mandarin WRF Recl. Water Transmission Pipeline Pkg 3 Greenland Substation to Butler Blvd Jacksonville, Florida	Jacksonville Electric Authority Groundworks 21 W Church Street Jacksonville, FL 32202 Mr. Robert Kermitz 904-665-6318	Install reclaimed water pipeline from Greenland Substation to Butler Blvd.	\$1,074,617	June 1, 2001 January 21, 2002
20086	Normandy Village Water Main Upgrade Jacksonville, Florida	Jacksonville Electric Authority Groundworks 21 W Church Street Jacksonville, FL 32202 Mr. Robert Kermitz 904-665-6318	Install new water main in the area between back of curb and right of way line and parallel to existing water main.	\$1,158,596	November 12, 2001 March 12, 2002
30015	Polk County Parkway Section 4A FDOT No. 201308-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consisted of clearing & grubbing, earthwork, associated storm drainage, associated waterline, bridge, stabilization, limerock asphalt (superpave), signage, lighting, pavement markings, and 2 each structural steel plate bridges on the new limited access road.	\$22,238,171	March 24, 1997 March 2, 2002
30023	118th Avenue Interchange CR 296 Extension Pinellas County FDOT No. 256894-1-52-01	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project consisted of new asphalt construction of 118 th Avenue N. (CR 296 Extension), I-275 Connector from 31 st Court North to I-275 for a distance of 943 meters in Pinellas County, and also included 119 FT AASHTO bulb T twin bridges, 897' AASHTO bulb T and steel ramp bridge, and a 1,309' steel plate girder bridge. The project also included 69,000 SF of re-wall.	\$21,728,124	*January 8, 2001 September 16, 2002



**HUBBARD CONSTRUCTION COMPANY
PROJECTS WORK COMPLETED IN 2002**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
30025	Dale Mabry Slab Rehab - SR 600 FDOT No. 255854-1-52-01 Hillsborough County Tampa, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The improvements to this contract consist of concrete pavement rehabilitation and widening of SR 600 (Dale Mabry Highway) from Kennedy Blvd. to MLK Blvd. in Tampa (Hillsborough County) Florida.	\$4,382,515	August 1, 2001 May 9, 2002
70005	SR 80 /Turnpike Interchange FDOT No. 23253-1-52-01 Palm Beach, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	This project required the removal of the existing bridge structure (2 structures) over the C-51 canal and replacement. Also, a new interchange with toll plazas was required. Temporary sheet piling, storm drainage, water and sanitary services, Roadway widening, milling and resurfacing, etc. approx 1.5 miles long.	\$20,269,907	*July 7, 1999 October 23, 2002
70007	Florida Turnpike Boca Raton to Delray FDOT No. 232513-1-52-01 Palm Beach, Florida	Florida Dept of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	The project included 5.87 miles of roadway with a new bridge over the Turnpike at Ramp AB (Boca Raton) and a new Turnpike bridge over Clint Moore Road. Also included two bridge widenings.	\$19,260,369	*July 17, 2000 August 31, 2002



HUBBARD CONSTRUCTION COMPANY
COMMERCIAL PRIVATE PROJECTS WORK IN PROGRESS

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	% COMPLETE
10325	Tuskawilla Middle School Seminole County	Seminole County Public School System c/o Suitt Construction Co 495 N Keller Road, STE 101 Maitland, FL 32751 407-834-2300 Mr. Darin Crafton	Project consists of demolition, earthwork, grading, asphalt pavement, storm drainage, sanitary sewer, fire lines, potable water, and electrical sleeves for the new school.	\$1,582,290	July 6, 2004 July 31, 2006	51%
10329	Gatorland Parking Lot Expansion	Godwin's Gatorland, Inc. 14501 S Orange Blossom Tr Orlando, FL 32837 407-855-5496 Mr. Mark McHugh	Demolition of existing parking lot and construction of new parking lot with storm drainage. Also included median modifications to SR 441.	\$463,801	October 4, 2004 February 2006	79%
10331	Target Orlando East	MCP Retail, Inc. 231 West Park Avenue Winter Park, FL 32789 407-599-4444 Mr. Mike Rich	Work consists of clearing, earthwork, grading, pavement and base, storm drainage, sanitary sewer, water and firemain, and flatwork.	\$2,188,739	October 4, 2004 February 2006	99%
10332	Florida Hospital South Bed Tower: Rollins Street Realignment, Aiden Garage, & Temporary Entrance Orlando, Florida	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D, Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Work consists of clearing trees and landscaping, traffic maintenance, demolition of pavement, curbs, sidewalks and certain utilities, storm drainage, sanitary sewer, water lines, paving and curbs and pavement markings.	\$1,856,717	November 23, 2004 March 2006	77%



HUBBARD CONSTRUCTION COMPANY
COMMERCIAL PRIVATE PROJECTS WORK IN PROGRESS

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	% COMPLETE
10333	Floridays Orlando Resort I-Drive/ Vineland Avenue Orlando, Florida	Floridays Development Corp 3700 South Tamiami Trail STE 201 Sarasota, FL 32216 941-362-9377 Mr. Mark Harvey	This project is a 20 acre site in which we will be doing clearing, earthwork and grading, pavement and curbing, storm drainage, sanitary sewer, retaining wall and sodding.	\$3,926,792	December 3, 2004 May 12, 2006	77%
10337	Florida Hospital Alden Garage	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of demolishing existing pavement and improvements, excavate for foundation and install drainage improvements.	\$126,886	November 8, 2004 January 2006	95%
10338	Florida Hospital Temporary Entrance	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of constructing a temporary entrance to Florida Hospital's main entry. Work included demolition, excavation and pavement.	\$424,248	January 14, 2005 January 2006	80%
10341	Florida Hospital Altamonte	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Project consists of parking lot and utility modifications. Work includes demolition, grading, storm drainage, utilities and pavement.	\$1,726,644	April 18, 2005 December 31, 2006	40%



HUBBARD CONSTRUCTION COMPANY
COMMERCIAL PRIVATE PROJECTS WORK IN PROGRESS

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	% COMPLETE
10342	Posner Park Access - 1A	Boardwalk and Baseball, Inc. C/O Kitson and Partners PO Box 992 Florham Park, NJ 07932 973-236-9600 John Broderick	Project includes a turn lane installation.	\$1,176,113	September 2005 March 2006	40%
10344	Posner City Center - 1B	Boardwalk and Baseball, Inc. C/O Kitson and Partners PO Box 992 Florham Park, NJ 07932 973-236-9600 John Broderick	Project consists of infrastructure road and utilities.	\$1,938,798		5%
10346	Florida Hospital South - Tower	Florida Hospital Office of Design & Construction c/o Brasfield & Gorrie 1919 N Orange Ave, STE D Orlando, FL 32804 407-562-4500 Mr. Peyton Robertson	Consists for site work for patient tower expansion.	\$2,736,922	November 1, 2005 September 19, 2009	1%
10349	Osceola Corporate Center Mary Louis Lane Roadway Development	Deerfield Land Corporation 14901 South Orange Blossom Trail Orlando, FL 32837 407-847-1846 Mr. Thomas M Roi	Construct new roadway with drainage. Reconstruct 1,800lf of Orange Avenue	\$1,718,518	January 2, 2006 May 31, 2006	1%
10350	Villages @ Imagine	Hardin-Led core Construction 4700 Millennia Blvd, STE 350 Orlando, FL 32839 407-353-2233 Mr. Don May	earthwork, utilities, drainage, paving and curbs.	\$4,376,000	January 3, 2006 November 2007	1%



HUBBARD CONSTRUCTION COMPANY
COMMERCIAL PRIVATE PROJECTS WORK IN PROGRESS

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE	% COMPLETE
70017	Super Target T-1935 SR 7 & Okeechobee Blvd Palm Beach County, FL	Target Corporation 1000 Nicolette Mall Minneapolis, MN 55403 904-347-3662 Mr. Joe Rozier, Owners Rep.	Project consists of sitework, earthwork grading, utilities, asphalt & concrete paving, concrete curbs & sidewalks, markings and offsite modifications on 21 acre site.	\$3,382,792	February 19, 2004 January 2006	96%
70020	Cobblestone Village @ ROB Okeechobee Blvd & SR 7	EMJ Corporation 2030 Hamilton Place Blvd. Suite 200 Chattanooga, Tenn. 37421 423-855-1550 Mr. Sam Wills	Project included site work on a 5 acre development for retail stores adjacent to Super Target	\$903,860	July 19, 2004 November 2005	90%
70021	Publix @ Polo Grounds Mall Military Trail & Summit Blvd	Hawkins Construction PO Box 1636 Tarpon Springs, FL 727-938-9719 ext. 266 Mr. Kenny King	Project involved demolition & construction of new Publix with associated site work.	\$1,050,000	August 20, 2004 January 2005	1%
70024	Target T-1941	Williams Company SE 2301 Silver Star Road Orlando, FL 32804 407-295-2530 Mr. Mike Ricotta	Project consists of development of a 20 acre site for a standard Target store	\$3,145,971	January 27, 2005 November 2005	97%



HUBBARD CONSTRUCTION COMPANY **COMMERCIAL-PRIVATE PROJECTS COMPLETED IN 2005**

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10324	SR 46 (OPC) FDOT # 240229 Seminole County, Florida	Florida Dept. of Transportation 605 Suwannee Street Haydon Burns Building Tallahassee, FL 32301 850-414-4000 Ms. Juanita Moore, Contracts	Road rehabilitation due to Hurricanes.	\$538,458	June 17, 2004 March 1, 2005
10326	Trinity Preparatory Track Expansion	Trinity Preparatory School 5700 Trinity Prep Lane Winter Park, FL 32792 407-671-4140	Project included Track expansion and improvements.	\$319,508	August 2, 2004 January 5, 2005
10328	Kissimmee Gateway Airport Blastpad	City of Kissimmee 301 N Dyer Road, Ste 101 Kissimmee, FL 34741 (407) 847-4600 Mr. Terry Lloyd	Project consists of grading and basework.	\$57,182	August 4, 2004 February 15, 2005




HUBBARD CONSTRUCTION COMPANY
COMMERCIAL PRIVATE PROJECTS COMPLETED IN 2003

12/30/05

HCC JOB NO.	CONTRACT NAME CONTRACT NUMBER	OWNER NAME AND ADDRESS CONTACT PERSON AND PHONE NO.	DESCRIPTION OF WORK	CONTRACT AMOUNT	START DATE/ COMPLETION DATE
10318	Little Lake Bryan Parcel 4 Osceola County, Florida Bid # 9041C-03LF	The Celebration Company PO Box 10321 Lake Buena Vista, FL 32830 407-566-4055 Fax 407-566-4388	Project included clearing, earthwork, storm drainage, landscape restorations, grassing, erosion control, and concrete sidewalks.	\$641,554	June 30, 2003 Sept. 30, 2003
70015	BAK Middle School 3701 North Shore Drive West Palm Beach, FL	Centex Rooney Construction Co, Inc. 7901 SW 6th Court Plantation, FL 33324 561-272-8375 ext 23 John Southard	Project included clearing & grubbing, earthwork & grading, asphalt pavement, concrete, storm drainage, sanitary sewer, water distribution system, pavement markings and signage.	\$541,076	August 14, 2003 November 1, 2003



THIS IS TO CERTIFY, that the Board of Directors of Hubbard Construction Company, at its June 8th, 2005 meeting, on motion duly made, seconded and unanimously carried, authorized Luc Bodson, Chairman of the Board, President & CEO, R. Wayne Evans, Senior Vice President, Business Development, Jean-Noel Velly, Senior Vice President, Construction Operations, or Ernest J. Wolf, Vice President, Contract Administration to execute Change Orders and Contracts on behalf of the Corporation.


P. Frederick O'Dea, Jr., Secretary

JUN 20 2005



Florida Department of Transportation

JEB BUSH
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JOSÉ ABREU
SECRETARY

June 15, 2005

Hubbard Construction Company
P. O. Box 547217
Orlando, FL 32854-7217

RE: CERTIFICATE OF QUALIFICATION

Gentlemen:

The Department of Transportation has qualified your company for the amount and the type of work indicated below. Unless your company is notified otherwise, this rating will expire June 30, 2006.

Please take notice that to ensure continuity in your certification at least thirty (30) days must be allowed for the processing of your next application for qualification. In accordance with S.337.14 (1) F.S. your next application must be filed within (4) months of the ending date of the applicant's audited annual financial statements and, if applicable, the audited interim financial statements. To remain qualified with the Department, a new application must be submitted subsequent to any significant change in the financial position or the structure of your firm as described in Section 14-22.005(3), Florida Administrative Code.

MAXIMUM CAPACITY RATING: \$756,400,000.00

WORK CLASS RATINGS:

1. Major Bridges:
 - a. Bridges which include Bascule Spans..... X
 - b. Bridges which include Curved Steel Girders..... X
 - c. Bridges with Multi-Level Roadways..... X
 - d. Bridges of Concrete Segmental Construction..... X
 - e. Bridges which include Steel Truss Construction.....
 - f. Bridges which include Cable Stayed Construction.....
 - g. Bridges of conventional construction which are over a water opening of 1000 feet or more..... X
2. Intermediate Bridges (Bridges that contain none of the type of construction listed under Major Bridges and span lengths exceeding 50 feet (center to center of cap)..... X
3. Minor Bridges (Bridges with span lengths not exceeding 50 feet (center to center of cap) and total length not exceeding 300 feet. A Minor Bridge shall not contain any types of construction listed under Major Bridges or Intermediate Bridges)..... X
4. Bascule Bridge Rehabilitation..... X
5. Grading (Includes clearing and grubbing, excavation, and embankment).... X
6. Drainage (Includes all storm drains, pipe culverts, culverts, etc.).... X
7. Flexible Paving (Includes limerock and shell base and other optional base courses, soil-cemented based, mixed-in-place bituminous paving, bituminous surface treatments, and stabilizing)..... X
8. Portland Cement Concrete Paving..... X
9. Hot Plant-Mixed Bituminous Structural and Surface Courses..... X


Hubbard Construction Company
June 15, 2005
Page Two

SPECIALTY CLASSES OR WORK:

Grassing, Seeding, Sodding, Pavement Marking, Roadway Signing, Wetland
Mitigation and Underground Utilities..... X

You may apply, in writing, for a Revised Certificate of Qualification at any time prior to the expiration date of this certificate according to Section 14-22.0041(3), Florida Administrative Code. Please be advised if certification in additional classes of work is desired, documentation is needed to show that your company has done such work with your own forces and equipment or that experience was gained with another contractor and that you have the necessary equipment for each additional class of work requested. Also, refer to the note at the bottom of Page 16 of the Application for Qualification when supplying additional information.

Sincerely yours,



Juanita Moore, Manager
Contracts Administration Office

JM:vap

12/89
(SEE NOTES ON REVERSE SIDE)