

**25. Approve Change Order #1 to CC-1234-04/TLR – Markham Road Widening from Markham Woods Road to Longwood-Markham Road with Florida Highway Products, Inc., Bartow (\$71,801.70).**

CC-1234-04/TLR provides for all labor, materials, equipment, transportation, coordination and incidentals necessary to complete the widening of Markham Road to two 12' lanes and micro-surfacing the entire roadway from Longwood-Markham Road to Markham Woods Road.

Based on the cost savings from the Longwood Markham Road project, this Change Order #1 will provide for re-construction of the missing gap between Markham Road and Longwood-Markham Road through the 90 degree curve to provide a homogeneous roadway with the same width along the whole corridor.

The following is a summary of the cost of the contract:

Original Contract Sum	\$269,996.00
Add Change Order #1	<u>71,801.70</u>
Revised Contract Sum	\$341,797.70

Pubic Works Department/Engineering Division and Fiscal Services Department/Purchasing and Contracts Division recommend that the Board approve and authorize the County Manager to execute Change Order #1.



**SEMINOLE COUNTY  
CHANGE ORDER ATTACHEMENT**

Project Name: Markham Road Widening Project/Agreement No. _CC 1234-04/TLR Change Order No. _1						
Item	Description	Qty	Unit	Unit Price	Qty Incr/Dec	Amount
999-1	To complete the construction of the missing link between Markham Rd and Longwood Markham Rd including the curve by scope reclaim, removal as necessary, pave, silt fence instillation, Maintenance of Traffic, Sod and Stripping	4377	SY	\$13		\$56,901.00
999-2	Replace Rusted Out Pipe Including: Removal of existing pipe, install 56 lf RCP class III, Install type C inlet, Modify existing inlet, Dewater as needed, return base to grade with reclaimed material	56	LF	\$266.08		\$14,900.70
<b>Total:</b>						<b>\$71,801.70</b>